

# AT21CS01/AT21CS11

# Single-Wire, I/O Powered 1-Kbit (128 x 8) Serial EEPROM with a Unique, Factory-Programmed 64-Bit Serial Number


# **Features**

- Low-Voltage Operation:
  - AT21CS01 is self-powered via the 1.7V to 3.6V pull-up voltage on the SI/O line
  - AT21CS11 is self-powered via the 2.7V to 4.5V pull-up voltage on the SI/O line
- Internally Organized as 128 x 8 (1 Kbit)
- Industrial Temperature Range: -40°C to +85°C
- Single-Wire Serial Interface with I<sup>2</sup>C Protocol Structure:
  - Device communication is achieved through a single I/O pin
- · Standard Speed and High-Speed Mode Options:
  - 15.4 kbps maximum bit rate in Standard Speed mode (AT21CS01 only)
  - 125 kbps maximum bit rate in High-Speed mode (AT21CS01 and AT21CS11)
- 8-Byte Page Write or Single Byte Writes Allowed
- · Discovery Response Feature for Quick Detection of Devices on the Bus
- ROM Zone Support:
  - Device is segmented into four 256-bit zones, each of which can be permanently made read-only (ROM)
- 256-Bit Security Register:
  - Lower eight bytes contain a factory-programmed, read-only, 64-bit serial number that is unique to all Microchip single-wire devices
  - Next eight bytes are reserved for future use and will read FFh
  - Upper 16 bytes are user-programmable and permanently lockable
- Self-Timed Write Cycle: 5 ms Maximum
- Manufacturer Identification Register:
  - Device responds with unique value for Microchip as well as density and revision information
- · High Reliability:
  - Endurance: 1,000,000 write cycles
  - Data retention: 100 years
  - IEC 61000-4-2 Level 4 ESD Compliant (±8 kV Contact, ±15 kV Air Discharge)
- Green (Lead-free/Halide-free/RoHS Compliant) Package Options
- Die Sale Options: Wafer Form and Tape and Reel

# **Packages**

2-Pad XSFN, 3-Lead SOT23, 8-Lead SOIC and 4-Ball WLCSP

# **Package Types**



# **Table of Contents**

Fea	atures	1
Pac	ckages	1
Pac	ckage Types	2
1.	Pin Descriptions	5
	1.1. Serial Input and Output	
	1.2. Ground	5
2.	Description	6
	2.1. System Configuration Using Single-Wire Serial EEPROMs	6
	2.2. Block Diagram	7
3.	Electrical Characteristics	8
	3.1. Absolute Maximum Ratings	8
	3.2. DC and AC Operating Range	
	3.3. AT21CS01 DC Characteristics <sup>(1)</sup>	
	3.4. AT21CS11 DC Characteristics <sup>(1)</sup>	
	3.5. AT21CS01/AT21CS11 AC Characteristics	10
4.	Device Operation and Communication	12
	4.1. Single-Wire Bus Transactions	12
5.	Device Addressing and I <sup>2</sup> C Protocol Emulation	17
	5.1. Memory Organization	17
6.	Available Opcodes	19
	6.1. EEPROM Access (Opcode Ah)	19
	6.2. Security Register Access (Opcode Bh)	
	6.3. Lock Security Register (Opcode 2h)	19
	6.4. ROM Zone Register Access (Opcode 7h)	19
	6.5. Freeze ROM Zone State (Opcode 1h)	
	6.6. Manufacturer ID Read (Opcode Ch)	
	6.7. Standard Speed Mode (Opcode Dh)	
	6.8. High-Speed Mode (Opcode Eh)	20
7.	Write Operations	21
	7.1. Device Behavior During Internal Write Cycle	21
	7.2. Byte Write	
	7.3. Page Write	
	7.4. Writing to the Security Register	
	7.5. Locking the Security Register	
	7.6. Setting the Device Speed	24
8.	Read Operations	25
	8.1. Current Address Read within the EEPROM	25
	8.2. Random Read within the EEPROM	25

	8.3.	Sequential Read within the EEPROM	26
	8.4.	Read Operations in the Security Register	26
	8.5.	Manufacturer ID Read	27
9.	ROM	Zones	29
	9.1.	ROM Zone Size and ROM Zone Registers	29
	9.2.	Programming and Reading the ROM Zone Registers	29
	9.3.	Device Response to a Write Operation Within an Enabled ROM Zone	31
10.	Devic	e Default Condition from Microchip	32
11.	Packa	aging Information	33
	11.1.	Package Marking Information	33
12.	Revis	ion History	42
The	Micro	chip Website	43
Pro	duct C	hange Notification Service	43
Cus	stomer	Support	43
Pro	duct Id	entification System	44
Mic	rochip	Devices Code Protection Feature	45
Leg	al Noti	ce	45
Tra	demark	(8	45
Qua	ality Ma	anagement System	46
Wo	rldwide	Sales and Service	47

# 1. Pin Descriptions

The descriptions of the pins are listed in Table 1-1.

**Table 1-1. Pin Function Table** 

Name	2-Pad XSFN	3-Lead SOT23	8-Lead SOIC	4-Ball WLCSP	Function
NC	_	_	1	_	No Connect
NC	_	_	2	_	No Connect
NC	_	2	3	B2	No Connect
GND	2	3	4	B1	Ground
SI/O	1	1	5	A1	Serial Input and Output
NC	_	<del>-</del>	6	A2	No Connect
NC	_	<del>-</del>	7	_	No Connect
NC	_	_	8	_	No Connect

# 1.1 Serial Input and Output

The SI/O pin is an open-drain, bidirectional input/output pin used to serially transfer data to and from the device. The SI/O pin must be pulled high using an external pull-up resistor and may be wire-ORed with any number of other open-drain or open-collector pins from other devices on the same bus. The device also uses the SI/O pin as its voltage source by drawing and storing power during the periods that the pin is pulled high to a voltage level between 1.7V to 3.6V (AT21CS01) and between 2.7V to 4.5V (AT21CS11).

# 1.2 Ground


The ground reference for the power supply. GND should be connected to the system ground.

# 2. Description


The AT21CS01/AT21CS11 is a 2-pin memory (SI/O and Ground) that harvests energy from the SI/O pin to power the integrated circuit. It provides 1,024 bits of Serial Electrically Erasable and Programmable Read-Only Memory (EEPROM) organized as 128 words of eight bits each.

The device is optimized to add configuration and use information in unpowered attachments using a two-point mechanical connection that brings only one signal (SI/O) and GND to the unpowered attachment. Some unpowered attachment application examples include analog sensor calibration data storage, ink and toner printer cartridge identification, and management of after-market consumables. The device's software addressing scheme allows up to eight devices to share a common single-wire bus. The device is available in space-saving package options and operates with an external pull-up voltage from 1.7V to 3.6V on the SI/O line (AT21CS01) or from 2.7V to 4.5V on the SI/O line (AT21CS01).

# 2.1 System Configuration Using Single-Wire Serial EEPROMs



# 2.2 Block Diagram



# 3. Electrical Characteristics

# 3.1 Absolute Maximum Ratings

Temperature under bias  $-55^{\circ}\text{C to } +125^{\circ}\text{C}$  Storage temperature  $-65^{\circ}\text{C to } +150^{\circ}\text{C}$  Voltage on any pin with respect to ground  $-0.6\text{V to V}_{\text{PUP}} +0.5\text{V}$ 

**DC output current** 15.0 mA

**Note:** Stresses above those listed under "Absolute Maximum Ratings" may cause permanent damage to the device. This is a stress rating only and functional operation of the device at these or any other conditions above those indicated in the operation listings of this specification is not implied. Exposure to absolute maximum rating conditions for extended periods may affect device reliability.

# 3.2 DC and AC Operating Range

Table 3-1. DC and AC Operating Range

		AT21CS01	AT21CS11
Operating Temperature (Case)	Industrial Temperature Range	-40°C to +85°C	-40°C to +85°C
V <sub>PUP</sub> Pull-up Voltage	Voltage Range	1.7V to 3.6V	2.7V to 4.5V

# 3.3 AT21CS01 DC Characteristics<sup>(1)</sup>

Parameter	Symbol	Minimum	Typical <sup>(2)</sup>	Maximum	Units	Test Conditions
Pull-up Voltage	$V_{PUP}$	1.7	_	3.6	V	High-Speed mode
		2.7	_	3.6	V	Standard Speed mode
Pull-up Resistance	R <sub>PUP</sub>	130	_	200	Ω	V <sub>PUP</sub> = 1.7V
		0.2	_	1.8	kΩ	V <sub>PUP</sub> = 2.7V
		0.33	_	4	kΩ	V <sub>PUP</sub> = 3.6V
Active Current, Read	I <sub>A1</sub>	_	0.08	0.3	mA	V <sub>PUP</sub> = 3.6V; SI/O = V <sub>PUP</sub>
Active Current, Write	I <sub>A2</sub>	_	0.2	0.5	mA	V <sub>PUP</sub> = 3.6V
Standby Current	I <sub>SB</sub>	_	0.6	1.5	μA	V <sub>PUP</sub> = 1.8V <sup>(3)</sup> ; SI/O = V <sub>PUP</sub>
		_	0.7	2.5	μA	V <sub>PUP</sub> = 3.6V
Input Low Level <sup>(3)(4)</sup>	V <sub>IL</sub>	-0.6	_	0.5	V	
Input High Level <sup>(3)(4)</sup>	V <sub>IH</sub>	V <sub>PUP</sub> x 0.7	_	V <sub>PUP</sub> + 0.5	V	
SI/O Hysteresis <sup>(3)(4)(5)</sup>	V <sub>HYS</sub>	0.128	_	1.17	V	
Output Low Level	V <sub>OL</sub>	0	_	0.4	V	I <sub>OL</sub> = 4 mA
Bus Capacitance	C <sub>BUS</sub>	_	_	1000	pF	

#### Notes:

- 1. Parameters are applicable over the operating range in DC and AC Operating Range, unless otherwise noted.
- 2. Typical values characterized at  $T_A = +25$ °C unless otherwise noted.
- This parameter is characterized but is not 100% tested in production.
- $V_{IH}$ ,  $V_{IL}$ , and  $V_{HYS}$  are a function of the internal supply voltage, which is a function of  $V_{PUP}$ ,  $R_{PUP}$ ,  $C_{BUS}$ , and timing used. Use of a lower  $V_{PUP}$ , higher  $R_{PUP}$ , higher  $C_{BUS}$ , and shorter  $t_{RCV}$  creates lower  $V_{IH}$ ,  $V_{IL}$  and  $V_{HYS}$
- Once VIH is crossed on a rising edge of SI/O, the voltage on SI/O must drop at least by VHYS to be detected as a logic '0'.

#### 3.4 AT21CS11 DC Characteristics(1)

Parameter	Symbol	Minimum	Typical <sup>(2)</sup>	Maximum	Units	Test Conditions
Pull-up Voltage	V <sub>PUP</sub>	2.7	_	4.5	V	High-Speed mode
Pull-up Resistance	R <sub>PUP</sub>	0.2	_	1.8	kΩ	V <sub>PUP</sub> = 2.7V
		0.4	_	5.4	kΩ	V <sub>PUP</sub> = 4.5V
Active Current, Read	I <sub>A1</sub>	_	0.08	0.3	mA	$V_{PUP} = 4.5V;$ SI/O = $V_{PUP}$
Active Current, Write	I <sub>A2</sub>	_	0.2	0.5	mA	V <sub>PUP</sub> = 4.5V
Standby Current	I <sub>SB</sub>	_	0.6	1.5	μA	$V_{PUP} = 2.7V^{(3)};$ SI/O = $V_{PUP}$
		_	0.7	3.0	μA	$V_{PUP} = 4.5V;$ SI/O = $V_{PUP}$
Input Low Level <sup>(3)(4)</sup>	V <sub>IL</sub>	-0.6	_	0.5	V	
Input High Level <sup>(3)(4)</sup>	V <sub>IH</sub>	V <sub>PUP</sub> x 0.7	_	V <sub>PUP</sub> + 0.5	V	
SI/O Hysteresis <sup>(3)(4)(5)</sup>	V <sub>HYS</sub>	0.128	_	1.4	V	
Output Low Level	V <sub>OL</sub>	0	_	0.4	V	I <sub>OL</sub> = 4 mA
Bus Capacitance	C <sub>BUS</sub>	_	_	1000	pF	

#### Notes:

- 1. Parameters are applicable over the operating range in DC and AC Operating Range, unless otherwise noted.
- Typical values characterized at  $T_A = +25$ °C unless otherwise noted. 2.
- This parameter is characterized but is not 100% tested in production.
- $V_{IH}$ ,  $V_{IL}$ , and  $V_{HYS}$  are a function of the internal supply voltage, which is a function of  $V_{PUP}$ ,  $R_{PUP}$ ,  $C_{BUS}$ , and timing used. Use of a lower  $V_{PUP}$ , higher  $R_{PUP}$ , higher  $C_{BUS}$ , and shorter  $t_{RCV}$  creates lower  $V_{IH}$ ,  $V_{IL}$  and  $V_{HYS}$
- Once VIH is crossed on a rising edge of SI/O, the voltage on SI/O must drop at least by VHYS to be detected as a logic '0'.

DS20005857D-page 9 © 2020 Microchip Technology Inc.

### 3.5 AT21CS01/AT21CS11 AC Characteristics

# 3.5.1 Reset and Discovery Response Timing

Parameter and Condition <sup>(1)(2)</sup>	Symbol	Symbol Standard Speed <sup>(3)(4)</sup>		Hig	Units	
		Min.	Max.	Min.	Max.	
Reset Low Time, Device in Inactive State	t <sub>RESET</sub>	480	_	96	_	μs
Discharge Low Time, Device in Active Write Cycle $(t_{\text{WR}})$	t <sub>DSCHG</sub>	150	_	150	_	μs
Reset Recovery Time	t <sub>RRT</sub>	N/A	N/A	8	_	μs
Discovery Response Request	t <sub>DRR</sub>	N/A	N/A	1	2 - t <sub>PUP</sub> <sup>(5)</sup>	μs
Discovery Response Acknowledge Time	t <sub>DACK</sub>	N/A	N/A	8	24	μs
Master Strobe Discovery Response Time	t <sub>MSDR</sub>	N/A	N/A	2	6	μs
SI/O High Time for Start/Stop Condition	t <sub>HTSS</sub>	N/A	N/A	150	_	μs

#### Notes:

- 1. Parameters applicable over operating range in DC and AC Operating Range, unless otherwise noted.
- 2. AC measurement conditions for the table above:
  - Loading capacitance on SI/O: 100 pF
  - $R_{PUP}$  (bus line pull-up resistor to  $V_{PUP}$ ): 1 k $\Omega$ ;  $V_{PUP}$ : 2.7V
- Due to the fact that the device will default to High-Speed mode upon Reset, the Reset and Discovery
  Response Timing after t<sub>RESET</sub> does not apply for Standard Speed mode. High-Speed mode timing applies in all
  cases after t<sub>RESET</sub>.
- 4. Standard Speed is not available on the AT21CS11.
- 5. t<sub>PUP</sub> is the time required once the SI/O line is released to be pulled up from V<sub>IL</sub> to V<sub>IH</sub>. This value is application specific and is a function of the loading capacitance on the SI/O line as well as the R<sub>PUP</sub> chosen. The use of additional slave devices adds capacitance to the SI/O line and should be taken into consideration. Limits for these values are provided in AT21CS01 DC Characteristics and AT21CS11 DC Characteristics.

# 3.5.2 Data Communication Timing

Parameter and Condition <sup>(1)(2)</sup>	Symbol	Frame Type	Standard Speed <sup>(3)</sup>		High S	peed	Units
			Min.	Max.	Min.	Max.	
Bit Frame Duration	t <sub>BIT</sub>	Input and Output Bit Frame	40	100	t <sub>LOW0</sub> + t <sub>PUP</sub> <sup>(4)</sup> + t <sub>RCV</sub>	25	μs
SI/O High Time for Start/Stop Condition	t <sub>HTSS</sub>	Input Bit Frame	600	_	150	_	μs
SI/O Low Time, Logic '0' Condition	t <sub>LOW0</sub>	Input Bit Frame	24	64	6	16	μs
SI/O Low Time, Logic '1' Condition	t <sub>LOW1</sub>	Input Bit Frame	4	8	1	2	μs
Master SI/O Low Time During Read	t <sub>RD</sub>	Output Bit Frame	4	8 - t <sub>PUP</sub> <sup>(4)</sup>	1	2 - t <sub>PUP</sub> <sup>(4)</sup>	μs

continued											
Parameter and Condition <sup>(1)(2)</sup>	Symbol	Frame Type	Standard	Standard Speed <sup>(3)</sup>		peed	Units				
			Min.	Max.	Min.	Max.					
Master Read Strobe Time	t <sub>MRS</sub>	Output Bit Frame	t <sub>RD</sub> + t <sub>PUP</sub> (4)	8	t <sub>RD</sub> + t <sub>PUP</sub> (4)	2	μs				
Data Output Hold Time (Logic '0')	t <sub>HLD0</sub>	Output Bit Frame	8	24	2	6	μs				
Slave Recovery Time	t <sub>RCV</sub>	Input and Output Bit Frame	8	_	2 <sup>(5)</sup>	_	μs				
Noise Filtering Capability on SI/O	t <sub>NOISE</sub>	Input Bit Frame	0.5		_		μs				

#### Notes:

- 1. Parameters applicable over operating range in DC and AC Operating Range, unless otherwise noted.
- 2. AC measurement conditions for the table above:
  - Loading capacitance on SI/O: 100 pF
  - $R_{PUP}$  (bus line pull-up resistor to  $V_{PUP}$ ): 1 k $\Omega$ ;  $V_{PUP}$ : 2.7V
- 3. Standard Speed is not available on the AT21CS11.
- 4. t<sub>PUP</sub> is the time required once the SI/O line is released to be pulled up from V<sub>IL</sub> to V<sub>IH</sub>. This value is application specific and is a function of the loading capacitance on the SI/O line as well as the R<sub>PUP</sub> chosen. The use of additional slave devices adds capacitance to the SI/O line and should be taken into consideration. Limits for these values are provided in AT21CS01 DC Characteristics and AT21CS11 DC Characteristics.
- 5. The system designer must select an combination of  $R_{PUP}$ ,  $C_{BUS}$ , and  $t_{BIT}$  such that the minimum  $t_{RCV}$  is satisfied. The relationship of  $t_{RCV}$  within the bit frame can be expressed by the following formula:  $t_{BIT} = t_{LOW0} + t_{PUP} + t_{RCV}$ .

#### 3.5.3 EEPROM Cell Performance Characteristics

Operation	Min.	Max.	Units	Test Condition
Write Cycle Time (t <sub>WR</sub> )	_	5	ms	V <sub>PUP</sub> (min.) < V <sub>PUP</sub> < V <sub>PUP</sub> (max.), T <sub>A</sub> = 25°C, Byte or Page Write mode
Write Endurance <sup>(1)</sup>	1,000,000	_	Write Cycles	V <sub>PUP</sub> (min.) < V <sub>PUP</sub> < V <sub>PUP</sub> (max.), T <sub>A</sub> = 25°C, Byte or Page Write mode
Data Retention <sup>(1)</sup>	100	_	Years	T <sub>A</sub> = 55°C

### Note:

1. Performance is determined through characterization and the qualification process.

# 4. Device Operation and Communication

The AT21CS01/11 operates as a slave device and utilizes a single-wire digital serial interface to communicate with a host controller, commonly referred to as the bus master. The master controls all read and write operations to the slave devices on the serial bus. The device has two speeds of operation, Standard Speed mode (AT21CS01) and High-Speed mode (AT21CS01 and AT21CS11).

The device utilizes an 8-bit data structure. Data is transferred to and from the device via the single-wire serial interface using the Serial Input/Output (SI/O) pin. Power to the device is also provided via the SI/O pin, thus only the SI/O pin and the GND pin are required for device operation. Data sent to the device over the single-wire bus is interpreted by the state of the SI/O pin during specific time intervals or slots. Each time slot is referred to as a bit frame and lasts  $t_{BIT}$  in duration. The master initiates all bit frames by driving the SI/O line low. All commands and data information are transferred with the Most Significant bit (MSb) first.

The software sequence sent to the device is an emulation of what would be sent to an  $I^2C$  Serial EEPROM with the exception that typical 4-bit device type identifier of 1010b in the device address is replaced by a 4-bit opcode. The device has been architected in this way to allow for rapid deployment and significant reuse of existing  $I^2C$  firmware. For more details about the way the device operates, refer to Device Addressing and  $I^2C$  Protocol Emulation.

During bus communication, one data bit is transmitted in every bit frame, and after eight bits (one byte) of data has been transferred, the receiving device must respond with either an Acknowledge (ACK) or a No Acknowledge (NACK) response bit during a ninth bit window. There are no unused clock cycles during any read or write operation, so there must not be any interruptions or breaks in the data stream during each data byte transfer and ACK or NACK clock cycle. In the event where an unavoidable system interrupt is required, refer to the requirements outlined in Communication Interruptions.

# 4.1 Single-Wire Bus Transactions

Types of data transmitted over the SI/O line:

- · Reset and Discovery Response
- Logic '0' or Acknowledge (ACK)
- Logic '1' or No Acknowledge (NACK)
- Start Condition
- · Stop Condition

The Reset and Discovery Response is not considered to be part of the data stream to the device, whereas the remaining four transactions are all required in order to send data to and receive data from the device. The difference between the different types of data stream transactions is the duration that SI/O is driven low within the bit frame.

### 4.1.1 Device Reset/Power-up and Discovery Response

### 4.1.1.1 Resetting the Device

A Reset and Discovery Response sequence is used by the master to reset the device as well as to perform a general bus call to determine if any devices are present on the bus.

To begin the Reset portion of the sequence, the master must drive SI/O low for a minimum time. If the device is not currently busy with other operations, the master can drive SI/O low for a time of t<sub>RESET</sub>. The length of t<sub>RESET</sub> differs for Standard Speed mode and for High-Speed mode.

However, if the device is busy, the master must drive SI/O for a time of  $t_{DSCHG}$  to ensure the device is reset as discussed in Interrupting the Device during an Active Operation. The Reset time forces any internal charge storage within the device to be consumed, causing the device to lose all remaining standby power available internally.

Upon SI/O being released for a sufficient amount of time to allow the device time to power-up and initialize, the master must then always request a Discovery Response Acknowledge from the AT21CS01/AT21CS11 prior to any commands being sent to the device. The master can then determine if an AT21CS01/AT21CS11 is present by sampling for the Discovery Response Acknowledge from the device.

#### 4.1.1.2 **Device Response Upon Reset or Power-Up**

After the device has been powered up or after the master has reset the device by holding the SI/O line low for t<sub>RESET</sub> or t<sub>DSCHG</sub>, the master must then release the line which will be pulled high by an external pull-up resistor. The master must then wait an additional minimum time of t<sub>RRT</sub> before the master can request a Discovery Response Acknowledge from the device.

The Discovery Response Acknowledge sequence begins by the master driving the SI/O line low which will start the AT21CS01/AT21CS11 internal timing circuits. The master must continue to drive the line low for t<sub>DRR</sub>.

During the t<sub>DRR</sub> time, the AT21CS01/AT21CS11 will respond by concurrently driving SI/O low. The device will continue to drive SI/O low for a total time of t<sub>DACK</sub>. The master should sample the state of the SI/O line at t<sub>MSDR</sub> past the initiation of t<sub>DRR</sub>. By definition, the t<sub>DACK</sub> minimum is longer than the t<sub>MSDR</sub> maximum time, thereby ensuring the master can always correctly sample the SI/O for a level less than  $V_{II}$ . After the  $t_{DACK}$  time has elapsed, the AT21CS01/AT21CS11 will release SI/O which will then be pulled high by the external pull-up resistor.

The master must then wait t<sub>HTSS</sub> to create a Start condition before continuing with the first command (see Start/Stop Condition for more details about Start conditions). By default, the device will come out of Reset in High-Speed mode. Changing the device to Standard Speed mode is covered in Standard Speed Mode (Opcode Dh).

The timing requirements for the Reset and Discovery Response sequence for both Standard Speed and High-Speed mode can be found in AT21CS01/AT21CS11 AC Characteristics.

#### 4.1.2 Interrupting the Device during an Active Operation

To conserve the stored energy within the onboard parasitic power system and minimize overall active current, the AT21CS01/AT21CS11 will not monitor the SI/O line for new commands while it is busy executing a previously sent command. As a result, the device is not able to sense how long SI/O has been in a given state. If the master requires to interrupt the device during an active operation, it must drive SI/O low long enough to deplete all of its remaining stored power. This time is defined as t<sub>DSCHG</sub>, after which a normal Discovery Response can begin by releasing the SI/O line.

AT21CS01 PULL-UP RESISTOR **MASTER** t<sub>HTSS</sub> Master Begin Next Sampling Command with SI/O t<sub>DRR</sub> Start Condition Window t<sub>RESET</sub> / t<sub>DSCHG</sub>  $t_{RRT}$ t<sub>MSDR</sub> **t**DACK

Figure 4-1. Reset and Discovery Response Waveform

#### 4.1.3 **Data Input and Output Bit Frames**

Communication with the AT21CS01/AT21CS11 is conducted in time intervals referred to as a bit frame and lasts t<sub>RIT</sub> in duration. Each bit frame contains a single binary data value. Input bit frames are used to transmit data from the master to the AT21CS01/AT21CS11 and can either be a logic '0' or a logic '1'. An output bit frame carries data from the AT21CS01/AT21CS11 to the master. In all input and output cases, the master initiates the bit frame by driving the SI/O line low. Once the AT21CS01/AT21CS11 detects the SI/O being driven below the V<sub>II</sub> level, its internal timing circuits begin to run.

The duration of each bit frame is allowed to vary from bit to bit as long as the variation does not cause the t<sub>BIT</sub> length to exceed the specified minimum and maximum values (see AT21CS01/AT21CS11 AC Characteristics). The t<sub>BIT</sub> requirements will vary depending on whether the device is set for Standard Speed or High-Speed mode. For more information about setting the speed of the device, refer to Setting the Device Speed.

#### 4.1.3.1 **Data Input Bit Frames**

A data input bit frame can be used by the master to transmit either a logic '0' or logic '1' data bit to the AT21CS01/ AT21CS11. The input bit frame is initiated when the master drives the SI/O line low. The length of time that the SI/O

**Datasheet** © 2020 Microchip Technology Inc.

# **Device Operation and Communication**

line is held low will dictate whether the master is transmitting a logic '0' or a logic '1' for that bit frame. For a logic '0' input, the length of time that the SI/O line must be held low is defined as  $t_{LOW0}$ . Similarly, for a logic '1' input, the length of time that the SI/O line must be held low is defined as  $t_{LOW1}$ .

The AT21CS01/AT21CS11 will sample the state of the SI/O line after the maximum  $t_{LOW1}$  but prior to the minimum  $t_{LOW0}$  after SI/O was driven below the  $V_{IL}$  threshold to determine if the data input is a logic '0' or a logic '1'. If the master is still driving the line low at the sample time, the AT21CS01/AT21CS11 will decode that bit frame as a logic '0' as SI/O will be at a voltage less than  $V_{IL}$ . If the master has already released the SI/O line, the AT21CS01/AT21CS11 will see a voltage level greater than or equal to  $V_{IH}$  because of the external pull-up resistor, and that bit frame will be decoded as a logic '1'. The timing requirements for these parameters can be found in AT21CS01/AT21CS11 AC Characteristics.

A logic '0' condition has multiple uses in the I<sup>2</sup>C emulation sequences. It is used to signify a '0' data bit, and it also is used for an Acknowledge (ACK) response. Additionally, a logic '1' condition is also is used for a No Acknowledge (NACK) response in addition to the nominal '1' data bit.

Figure 4-2 and Figure 4-3 depict the logic '0' and logic '1' input bit frames.

Figure 4-2. Logic '0' Input Condition Waveform





Figure 4-3. Logic '1' Input Condition Waveform



# 4.1.3.2 Start/Stop Condition

All transactions to the AT21CS01/AT21CS11 begin with a Start condition; therefore, a Start can only be transmitted by the master to the slave. Likewise, all transactions are terminated with a Stop condition and thus a Stop condition can only be transmitted by the master to the slave.


The Start and Stop conditions require identical biasing of the SI/O line. The Start/Stop condition is created by holding the SI/O line at a voltage of  $V_{PUP}$  for a duration of  $t_{HTSS}$ . Refer to AT21CS01/AT21CS11 AC Characteristics for timing minimums and maximums.

Figure 4-4 and Figure 4-5 depict the Start and Stop conditions.

Figure 4-4. Start Condition Waveform



Figure 4-5. Stop Condition Waveform



### 4.1.3.3 Communication Interruptions

In the event that a protocol sequence is interrupted midstream, this sequence can be resumed at the point of interruption if the elapsed time of inactivity (where SI/O is idle) is less that the maximum  $t_{BIT}$  time. The maximum allowed value will differ if the device is High-Speed mode or Standard Speed mode (see Setting the Device Speed). Note: The interruption of protocol must not occur during a write sequence immediately after a logic '0' (ACK response) when sending data to be written to the device. In this case, the interruption will be interpreted as a Stop condition and will cause an internal write cycle to begin. The device will be busy for  $t_{WR}$  time and will not respond to any commands.

For systems that cannot accurately monitor the location of interrupts, it is recommended to ensure that a minimum interruption time be observed consistent with the longest busy operation of the device  $(t_{WR})$ . Communicating with the device while it is in an internal write cycle by the master driving SI/O low could cause the byte(s) being written to become corrupted and must be avoided. The behavior of the device during a write cycle is described in more detail in Device Behavior During Internal Write Cycles.

If the sequence is interrupted for longer than the maximum  $t_{BIT}$ , the master must wait at least the minimum  $t_{HTSS}$  before continuing. By waiting the minimum  $t_{HTSS}$  time, a new Start condition is created and the device is ready to receive a new command. It is recommended that the master start over and repeat the transaction that was interrupted midstream.

### 4.1.3.4 Data Output Bit Frame

A data output bit frame is used when the master is to receive communication back from the AT21CS01/AT21CS11. Data output bit frames are used when reading any data out as well as any ACK or NACK responses from the device. Just as in the input bit frame, the master initiates the sequence by driving the SI/O line below the  $V_{\rm IL}$  threshold which engages the AT21CS01/AT21CS11 internal timing generation circuit.


Within the output bit frame is the critical timing parameter  $t_{RD}$ , which is defined as the amount of time the master must continue to drive the SI/O line low after crossing the below  $V_{IL}$  threshold to request a data bit back from the AT21CS01/AT21CS11. Once the  $t_{RD}$  duration has expired, the master must release the SI/O line.

If the AT21CS01/AT21CS11 is responding with a logic '0' (for either a '0' data bit or an ACK response), it will begin to pull the SI/O line low concurrently during the  $t_{RD}$  window and continue to hold it low for a duration of  $t_{HLD0}$ , after which it will release the line to be pulled back up to  $V_{PUP}$  (see Figure 4-6). Thus, when the master samples SI/O within the

# **Device Operation and Communication**

 $t_{MRS}$  window, it will see a voltage less than  $V_{IL}$  and decode this event as a logic '0'. By definition, the  $t_{HLD0}$  time is longer than the  $t_{MRS}$  time and therefore, the master is ensured to sample while the AT21CS01/AT21CS11 is still driving the SI/O line low.


Figure 4-6. Logic '0' Data Output Bit Frame Waveform



If the AT21CS01/AT21CS11 intends to respond with a logic '1' (for either a '1' data bit or a NACK response), it will not drive the SI/O line low at all. Once the master releases the SI/O line after the maximum  $t_{RD}$  has elapsed, the line will be pulled up to  $V_{PUP}$ . Thus, when the master samples the SI/O line within the  $t_{MRS}$  window, it will detect a voltage greater than  $V_{IH}$  and decode this event as a logic '1'.

The data output bit frame is shown in greater detail below in Figure 4-7.

Figure 4-7. Logic '1' Data Output Bit Frame Waveform



# 5. Device Addressing and I<sup>2</sup>C Protocol Emulation

Accessing the device requires a Start condition followed by an 8-bit device address byte.

The single-wire protocol sequence emulates what would be required for an I<sup>2</sup>C Serial EEPROM, with the exception that the beginning four bits of the device address are used as an opcode for the different commands and actions that the device can perform.

Since multiple slave devices can reside on the bus, each slave device must have its own unique address so that the master can access each device independently. After the 4-bit opcode, the following three bits of the device address byte are comprised of the slave address bits. The three slave address bits are preprogrammed prior to shipment. Obtaining devices with different slave address bit values is done by purchasing a specific ordering code. Refer to Packaging Information for explanation of which ordering code corresponds with a specific slave address value.

Following the three slave address bits is a Read/Write select bit where a logic '1' indicates a read and a logic '0' indicates a write. Upon the successful comparison of the device address byte, the EEPROM will return an ACK (logic '0'). If the 4-bit opcode is invalid or the three bits of slave address do not match what is preprogrammed in the device, the device will not respond on the SI/O line and will return to a Standby state.

Table 5-1. Device Address Byte

	4-bit C	pcode		Preprogr	Preprogrammed Slave Address Bits				
Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 3 Bit 2 Bit 1				
Ref	Refer to Available Opcodes			A2	A1	A0	R/W		

Following the device address byte, a memory address byte must be transmitted to the device immediately. The memory address byte contains a 7-bit memory array address to specify which location in the EEPROM to start reading or writing. Refer to Table 5-2 to review these bit positions.

Table 5-2. Memory Address Byte

Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0
Don't Care	A6	A5	A4	A3	A2	A1	A0

# 5.1 Memory Organization

The AT21CS01/AT21CS11 internal memory array is partitioned into two regions. The main 1-Kbit EEPROM is organized as 16 pages of eight bytes each. The Security register is 256 bits in length, organized as four pages of eight bytes each. The lower two pages of the Security register are read-only and have a factory-programmed, 64-bit serial number that is unique across all AT21CS Series serial EEPROMs. The upper two pages of the Security register are user-programmable and can be subsequently locked (see Locking the Security Register).

Figure 5-1. Memory Architecture Diagram

# 1-Kbit Address Range (00h-7Fh)

Main 1-Kbit EEPROM Opcode 1010b (Ah)	Zone 0	
	Zone 1	Four, 256-bit
	Zone 2	Each can be independently
	Zone 3	set to read-only
256-bit Security Register Opcode 1011b (Bh)	64-bit Serial Number Address Range (00h-07h)	Read-Only
	Reserved for Future Use Address Range (08h-0Fh)	Read Offiny
	User-Programmable Memory Address Range (10h-1Fh)	Permanently Lockable by Software

#### 6. **Available Opcodes**

Table 6-1 outlines available opcodes for the AT21CS01/AT21CS11.

Table 6-1. Opcodes used by the AT21CS01/AT21CS11

Command	4-Bit Opcode	Brief Description of Functionality
EEPROM Access	1010 <b>(Ah)</b>	Read/Write the contents of the main memory array.
Security Register Access	1011 <b>(Bh)</b>	Read/Write the contents of the Security register.
Lock Security Register	0010 <b>(2h)</b>	Permanently lock the contents of the Security register.
ROM Zone Register Access	0111 <b>(7h)</b>	Inhibit further modification to a zone of the EEPROM array.
Freeze ROM Zone State	0001 <b>(1h)</b>	Permanently lock the current state of the ROM Zone registers.
Manufacturer ID Read	1100 <b>(Ch)</b>	Query manufacturer and density of device.
Standard Speed Mode	1101 <b>(Dh)</b>	Switch to Standard Speed mode operation (AT21CS01 only command, the AT21CS11 will NACK this command).
High-Speed Mode	1110 <b>(Eh)</b>	Switch to High-Speed mode operation (AT21CS01 power-on default. AT21CS11 will ACK this command).

#### 6.1 **EEPROM Access (Opcode Ah)**

The opcode Ah is used to read data from and write data to the EEPROM. Refer to Read Operations for more details about reading data from the device. For details about writing to the EEPROM, refer to Write Operations.

#### 6.2 **Security Register Access (Opcode Bh)**

The opcode Bh is used to read data from and write data to the Security register. Refer to Read Operations in the Security Register for more details about reading data from the Security register. For details about writing to the userprogrammable portion of the Security register, refer to section Writing to the Security Register.

#### 6.3 Lock Security Register (Opcode 2h)

The opcode 2h is used to permanently lock the user-programmable portion of the Security register. Refer to Locking the Security Register.

#### 6.4 ROM Zone Register Access (Opcode 7h)

The AT21CS01/AT21CS11 is partitioned into four, 256-bit zones, each of which can be independently and permanently made read-only (ROM). The state of each zone is stored in a register which can be read from or written to using the opcode 7h. The ROM Zone functionality is explained in greater detail in ROM Zones.

#### 6.5 Freeze ROM Zone State (Opcode 1h)

The opcode 1h is used to permanently freeze the current state of the ROM Zone registers. Once set, the ROM Zone registers are read-only. Therefore, any zone that is not already read-only cannot be subsequently converted to ROM. Refer to Freeze ROM Zone Registers for additional details.

© 2020 Microchip Technology Inc.

# 6.6 Manufacturer ID Read (Opcode Ch)

Manufacturer identification, device density, and device revision information can be read from the device using the opcode Ch. The full details of the format of the data returned by this command are found in Manufacturer ID Read.

# 6.7 Standard Speed Mode (Opcode Dh)

The AT21CS01 can be set to Standard Speed mode or checked to see whether or not it is in Standard Speed mode with the use of the Dh opcode. Further details are covered in Standard Speed Mode (AT21CS01 only). The AT21CS11 does not offer Standard Speed mode and therefore will NACK this command.

# 6.8 High-Speed Mode (Opcode Eh)

The AT21CS01 can be set to High-Speed mode or checked to see whether or not it is in High-Speed mode with the use of the Eh opcode. The AT21CS11 only operates in High-Speed mode and therefore will ACK this command. Further details are covered in High-Speed Mode.

#### 7. Write Operations

All write operations to the AT21CS01/AT21CS11 begin with the master sending a Start condition, followed by a device address byte (opcode Ah for the EEPROM and opcode Bh for the Security register) with the R/W bit set to '0' followed by the memory address byte. Next, the data value(s) to be written to the device are sent. Data values must be sent in 8-bit increments to the device followed by a Stop condition. If a Stop condition is sent somewhere other than at the byte boundary, the current write operation will be aborted. The AT21CS01/AT21CS11 allows single byte writes, partial page writes, and full page writes.

#### 7.1 **Device Behavior During Internal Write Cycle**

To ensure that the address and data sent to the device for writing are not corrupted while any type of internal write operation is in progress, commands sent to the device are blocked from being recognized until the internal operation is completed. If a write interruption occurs (SI/O pulsed low) and is small enough to not deplete the internal power storage, the device will NACK signaling that the operation is in progress. If an interruption is longer than t<sub>DSCHG</sub> then internal write operation will be terminated and may result in data corruption.

#### 7.2 Byte Write

The AT21CS01/AT21CS11 supports writing of a single 8-bit byte and requires a 7-bit memory word address to select which byte to write.

Upon receipt of the proper device address byte (with opcode of Ah) and memory address byte, the EEPROM will send a logic '0' to signify an ACK. The device will then be ready to receive the data byte. Following receipt of the complete 8-bit data byte, the EEPROM will respond with an ACK. A Stop condition must then occur; however, since a Stop condition is defined as a null bit frame with SI/O pulled high, the master does not need to drive the SI/O line to accomplish this. If a Stop condition is sent at any other time, the write operation is aborted. After the Stop condition is complete, the EEPROM will enter an internally self-timed write cycle, which will complete within a time of twR, while the data is being programmed into the nonvolatile EEPROM. The SI/O pin must be pulled high via the external pullup resistor during the entire two cycle. Thus, in a multi-slave environment, communication to other single-wire devices on the bus should not be attempted while any devices are in an internal write cycle. After the maximum twR time has elapsed, the master may begin a new bus transaction.

Note: Any attempt to interrupt the internal write cycle by driving the SI/O line low may cause the byte being programmed to be corrupted. Other memory locations within the memory array will not be affected. Refer to Device Behavior During Internal Write Cycle for the behavior of the device while the write cycle is in progress. If the master must interrupt a write operation, the SI/O line must be driven low for t<sub>DSCHG</sub> as noted in Interrupting the Device during an Active Operation.

Figure 7-1. Byte Write



**Note:** x = Don't Care bit in the place of A7 as this bit falls outside the 1-Kbit addressable range.

#### 7.3 **Page Write**

A page write operation allows up to eight bytes to be written in the same write cycle, provided all bytes are in the same row (address bits A6 through A3 are the same) of the memory array. Partial page writes of less than eight bytes are allowed.

A page write is initiated the same way as a byte write, but the bus master does not send a Stop condition after the first data byte is clocked in. Instead, after the EEPROM Acknowledges receipt of the first data byte, the bus master can transmit up to an additional seven data bytes.


**Datasheet** © 2020 Microchip Technology Inc.

The EEPROM will respond with an ACK after each data byte is received. Once all data bytes have been sent, the device requires a Stop condition to begin the write cycle. However, since a Stop condition is defined as a null bit frame with SI/O pulled high, the master does not need to drive the SI/O line to accomplish this. If a Stop condition is sent at any other time, the write operation is aborted. After the Stop condition is complete, the internally self-timed write cycle will begin. The SI/O pin must be pulled high via the external pull-up resistor during the entire  $t_{WR}$  cycle. Thus, in a multi-slave environment, communication to other single-wire devices on the bus should not be attempted while any devices are in an internal write cycle. After the maximum  $t_{WR}$  time has elapsed, the master may begin a new bus transaction.

The lower three bits of the memory address are internally incremented following the receipt of each data byte. The higher order address bits are not incremented, and the device retains the memory page location. Page write operations are limited to writing bytes within a single physical page, regardless of the number of bytes actually being written. When the incremented word address reaches the page boundary, the address counter will "roll over" to the beginning of the same page. Nevertheless, creating a roll over event should be avoided as previously loaded data in the page could become unintentionally altered.

**Note:** Any attempt to interrupt the internal write cycle by driving the SI/O line low may cause the bytes being programmed to be corrupted. Other memory locations within the memory array will not be affected. Refer to Device Behavior During Internal Write Cycle for the behavior of the device while the write cycle is in progress. If the master must interrupt a write operation, the SI/O line must be driven low for t<sub>DSCHG</sub> as noted in Interrupting the Device during an Active Operation.

Figure 7-2. Page Write



**Note:** x = Don't Care bit in the place of A7 as this bit falls outside the 1-Kbit addressable range.

### 7.4 Writing to the Security Register

The Security register supports bytes writes, page writes, and partial page writes in the upper 16 bytes (upper two pages of eight bytes each) of the region. Page writes and partial page writes in the Security register have the same page boundary restrictions and behavior requirements as they do in the EEPROM.

Upon receipt of the proper device address byte (with opcode of Bh specified) and memory address byte, the EEPROM will send a logic '0' to signify an ACK. The device will then be ready to receive the first data byte.

Following receipt of the data byte, the EEPROM will respond with an ACK and the master can send up to an additional seven bytes if desired. The EEPROM will respond with an ACK after each data byte is successfully received. Once all of the data bytes have been sent, the device requires a Stop condition to begin the write cycle. However, since a Stop condition is defined as a null bit frame with SI/O pulled high, the master does not need to drive the SI/O line to accomplish this. After the Stop condition is complete, the EEPROM will enter an internally self-timed write cycle, which will complete within a time of  $t_{WR}$ , while the data is being programmed into the nonvolatile EEPROM. The SI/O pin must be pulled high via the external pull-up resistor during the entire  $t_{WR}$  cycle. Thus, in a multi-slave environment, communication to other single-wire devices on the bus should not be attempted while any devices are in an internal write cycle. Figure 7-3 is included below as an example of a byte write operation in the Security register.

Figure 7-3. Byte Write in the Security Register



#### Notes:

- x = Don't Care values in the place of A7-A5 as these bits falls outside the addressable range of the Security register.
- 2. Any attempt to interrupt the internal write cycle by driving the SI/O line low may cause the byte being programmed to be corrupted. Other memory locations within the memory array will not be affected. Refer to Device Behavior During Internal Write Cycle for the behavior of the device while the write cycle is in progress. If the master must interrupt a write operation, the SI/O line must be driven low for t<sub>DSCHG</sub> as noted in Interrupting the Device during an Active Operation.

# 7.5 Locking the Security Register

The Lock command is an irreversible sequence that will permanently prevent all future writing to the upper 16 bytes of the Security register on the AT21CS01/AT21CS11. Once the Lock command has been executed, the entire 32-byte Security register becomes read-only. Once the Security register has been locked, it is not possible to unlock it.

The Lock command protocol emulates a byte write operation to the Security register, however, the opcode 0010b (2h) is required along with the A7 through A4 bits of the memory address being set to 0110b (6h). The remaining bits of the memory address, as well as the data byte are "don't care" bits. Even though these bits are "don't cares", they still must be transmitted to the device. An ACK response to the memory address and data byte indicates the Security register is not currently locked. A NACK response indicates the Security register is already locked. Refer to Check Lock Command for details about determining the Lock status of the Security register.

The sequence completes with a Stop condition to initiate a self-timed internal write cycle. If a Stop condition is sent at any other time, the Lock operation is aborted. Since a Stop condition is defined as a null bit frame with SI/O pulled high, the master does not need to drive the SI/O line to accomplish this. Upon completion of the write cycle, (taking a time of t<sub>WR</sub>), the Lock operation is complete and the Security register will become permanently read-only.

**Note:** Any attempt to drive the SI/O line low during the t<sub>WR</sub> time period may cause the Lock operation to not complete successfully, and must be avoided.

Figure 7-4. Lock Command




#### 7.5.1 Device Response to a Write Operation on a Locked Device

A locked device will respond differently to a write operation to the Security register compared to a device that has not been locked. Writing to the Security register is accomplished by sending a Start condition followed by a device address byte with the opcode of 1011b (Bh), the appropriate slave address combination, and the Read/Write bit set as a logic '0'. Both a locked device and a device that has not been locked will return an ACK. Next, the 8-bit word address is sent and again, both devices will return an ACK. However, upon sending the data input byte, a device that has already been locked will return a NACK and be immediately ready to accept a new command, whereas a device that has not been locked will return an ACK to the data input byte as per normal operation for a write operation as described in Write Operations.

#### 7.5.2 Check Lock Command

The Check Lock command follows the same sequence as the Lock command (including 0110b in the A7 through A4 bits of the memory address byte) with the exception that only the device address byte and memory address byte need to be transmitted to the device. An ACK response to the memory address byte indicates that the lock has not been set while a NACK response indicates that the lock has been set. If the lock has already been enabled, it cannot be reversed. The Check Lock command is completed by the master sending a Stop bit to the device (defined as a null bit frame).

Figure 7-5. Check Lock Command



# 7.6 Setting the Device Speed

The AT21CS01 can be set to Standard Speed mode (15.4 kbps maximum) or High-Speed mode (125 kbps maximum) through a software sequence. Upon executing a Reset and Discovery Response sequence (see Device Reset/Power-up and Discovery Response), the device will default to High-Speed mode. The AT21CS11 does not have Standard Speed mode.

### 7.6.1 Standard Speed Mode (AT21CS01 only)

The AT21CS01 can be set to Standard Speed mode or checked to see whether or not it is in Standard Speed mode with the use of the Dh opcode. This transaction only requires eight bits.

To set the device to Standard Speed mode, the master must send a Start condition, followed by the device address byte with the opcode of 1101b (Dh) specified, along with the appropriate slave address combination and the Read/ Write bit set to a logic '0'. The device will return an ACK (logic '0') and will be immediately ready to receive commands for standard speed operation.

To determine if the device is already set to Standard Speed mode, the device address byte with the opcode of 1101b (Dh) must be sent to the device, along with the appropriate slave address combination and the Read/Write bit set to a logic '1'. The device will return an ACK (logic '0') if it was set for Standard Speed mode. It will return a NACK (logic '1') if the device was not currently set for Standard Speed mode.

Note: The AT21CS11 will NACK this command.

### 7.6.2 High-Speed Mode

The device can be set to High-Speed mode or checked to see whether or not it is in High-Speed mode with the use of the Eh opcode. This transaction only requires eight bits. The power-on default for the AT21CS01/AT21CS11 is High-Speed mode.

To set the device to High-Speed mode, the master must send a Start condition, followed by the device address byte with the opcode of 1110b (Eh) specified, along the appropriate slave address combination and the Read/Write bit set to a logic '0'. The device will return an ACK (logic '0') and will be immediately ready to receive commands for high-speed operation.

To determine if the device is already set to High-Speed mode, the device address byte with the opcode of 1110b (Eh) specified must be sent to the device along with the appropriate slave address combination and the Read/Write bit set to a logic '1'. The device will return an ACK (logic '0') if it was set for High-Speed mode. It will return a NACK (logic '1') if the device was not currently set for High-Speed mode.

Note: The AT21CS11 will ACK this command.

# 8. Read Operations

Read operations are initiated in a similar way as write operations with the exception that the Read/Write select bit in the device address byte must be set to a logic '1'. There are multiple read operations supported by the device:

- Current Address Read within the EEPROM
- · Random Read within the EEPROM
- · Sequential Read within the EEPROM
- · Read from the Security Register
- · Manufacturer ID Read

**Note:** The AT21CS01/AT21CS11 contains a single, shared-memory Address Pointer that maintains the address of the next byte in the EEPROM or Security register to be accessed. For example, if the last byte read was memory location 0Dh of the EEPROM, then the Address Pointer will be pointing to memory location 0Eh of the EEPROM. As such, when changing from a read in one region to the other, the first read operation in the new region should begin with a random read instead of a current address read to ensure the Address Pointer is set to a known value within the desired region.

If the end of the EEPROM or the Security register is reached, then the Address Pointer will "roll over" back to the beginning address of that region. The Address Pointer retains its value between operations as long as the pull-up voltage on the SI/O pin is maintained or as long as the device has not been reset.

### 8.1 Current Address Read within the EEPROM

The internal Address Pointer must be pointing to a memory location within the EEPROM in order to perform a current address read from the EEPROM. To initiate the operation, the master must send a Start condition, followed by the device address byte with the opcode of 1010b (Ah) specified, along with the appropriate slave address combination and the Read/Write bit set to a logic '1'. After the device address byte has been sent, the AT21CS01/AT21CS11 will return an ACK (logic '0').


Following the ACK, the device is ready to output one byte (eight bits) of data. The master initiates the all bits of data by driving the SI/O line low to start. The AT21CS01/AT21CS11 will hold the line low after the master releases it to indicate a logic '0'. If the data is logic '1', the AT21CS01/AT21CS11 will not hold the SI/O line low at all, causing it to be pulled high by the pull-up resistor once the master releases it. This sequence repeats for eight bits.

After the master has read the first data byte and no further data is desired, the master must return a NACK (logic '1') response to end the read operation and return the device to the Standby mode. Figure 8-1 depicts this sequence.

If the master would like the subsequent byte, it would return an ACK (logic '0') and the device will be ready output the next byte in the memory array. Refer to Sequential Read within the EEPROM for details about continuing to read beyond one byte.

**Note:** If the last operation to the device was an access to the Security register, then a random read should be performed to ensure that the Address Pointer is set to a known memory location within the EEPROM.

Figure 8-1. Current Address Read




# 8.2 Random Read within the EEPROM

A random read begins in the same way as a byte write operation which will load a new EEPROM memory address into the Address Pointer. However, instead of sending the data byte and Stop condition of the byte write, a repeated Start condition is sent to the device. This sequence is referred to as a "dummy write". After the device address and

memory address bytes of the "dummy write" have been sent, the AT21CS01/AT21CS11 will return an ACK response. The master can then initiate a current address read, beginning with a new Start condition, to read data from the EEPROM. Refer to Figure 8-2 for details on how to perform a current address read.

Figure 8-2. Random Read



# 8.3 Seguential Read within the EEPROM

Sequential reads start as either a current address read or as a random read. However, instead of the master sending a NACK (logic '1') response to end a read operation after a single byte of data has been read, the master sends an ACK (logic '0') to instruct the AT21CS01/AT21CS11 to output another byte of data. As long as the device receives an ACK from the master after each byte of data has been output, it will continue to increment the address counter and output the next byte data from the EEPROM. If the end of the EEPROM is reached, then the Address Pointer will "roll over" back to the beginning (address 00h) of the EEPROM region. To end the sequential read operation, the master must send a NACK response after the device has output a complete byte of data. After the device receives the NACK, it will end the read operation and return to the Standby mode.

**Note:** If the last operation to the device accessed the Security register, then a random read should be performed to ensure that the Address Pointer is set to a known memory location within the EEPROM.

Figure 8-3. Sequential Read from a Current Address Read





Figure 8-4. Sequential Read from a Random Read



# 8.4 Read Operations in the Security Register

The Security register can be read by using either a random read or a sequential read operation. Due to the fact that the EEPROM and Security register share a single Address Pointer register, a "dummy write" must be performed to correctly set the Address Pointer in the Security register. This is why a random read or sequential read must be used

as these sequences include a "dummy write." Bits A7 through A5 are "don't care" bits as these fall outside the addressable range of the Security register. Current address reads of the Security register are not supported.

In order to read the Security register, the device address byte must be specified with the opcode 1011b (Bh) instead of the opcode 1010b (Ah). The Security register can be read to read the 64-bit serial number or the remaining userprogrammable data.

#### 8.4.1 Serial Number Read

The lower eight bytes of the Security register contain a factory-programmed, unique, 64-bit serial number. In order to ensure a unique value, the entire 64-bit serial number must be read starting at Security register address location 00h. Therefore, it is recommended that a sequential read started with a random read operation be used, ensuring that the random read sequence uses a device address byte with opcode 1011b (Bh) specified in addition to the memory address byte being set to 00h.


The first byte read out of the 64-bit serial number is the product identifier (A0h). Following the product identifier, a 48bit unique number is contained in bytes 1 through 6. The last byte of the serial number contains a cyclic redundancy check (CRC) of the other 56 bits. The CRC is generated using the polynomial  $X^8 + X^5 + X^4 + 1$ . The structure of the 64-bit serial number is depicted in Table 8-1.

Table 8-1. 64-Bit Factory-Programmed Serial Number Organization

Byte 0	Byte 1	Byte 2	Byte 3	Byte 4	Byte 5	Byte 6	Byte 7
8-bit Product Identifier (A0h)			48-bit Uni	que Number			8-bit CRC Value

After all eight bytes of the serial number have been read, the master can return a NACK (logic '1') response to end the read operation and return the device to the Standby mode. If the master sends an ACK (logic '0') instead of a NACK, then the next byte (address location 08h) in the Security register will be output. If the end of the Security register is reached, then the Address Pointer will "roll over" back to the beginning (address location 00h) of the Security register.

Figure 8-5. Serial Number Read



#### 8.5 Manufacturer ID Read

The AT21CS01/AT21CS11 offers the ability to query the device for manufacturer, density, and revision information. By using a specific opcode and following the format of a current address read, the device will return a 24-bit value that corresponds with the I<sup>2</sup>C identifier value reserved for Microchip, along with further data to signify a 1-Kbit density and the device revision.

To read the Manufacturer ID data, the master must send a Start condition, followed by the device address byte with the opcode of 1100b (Ch) specified, along the appropriate slave address combination and the Read/Write bit set to a logic '1'. After the device address byte has been sent, the AT21CS01/AT21CS11 will return an ACK (logic '0'). If the

**Datasheet** © 2020 Microchip Technology Inc.

Read/Write bit is set to a logic '0' to indicate a write, the device will NACK (logic '1') since the Manufacturer ID data is read-only.

After the device has returned an ACK, it will then send the first byte of Manufacturer ID data which contains the eight Most Significant bits (D23-D16) of the 24-bit data value. The master can then return an ACK (logic '0') to indicate it successfully received the data, upon which the device will send the second byte (D15-D8) of Manufacturer ID data. The process repeats until all three bytes have been read out and the master sends a NACK (logic '1') to complete the sequence. Figure 8-6 depicts this sequence below. If the master ACKs (logic '0') the third byte, the Internal Pointer will "roll over" back to the first byte of Manufacturer ID data.

Figure 8-6. Manufacturer ID Read




Table 8-2 below provides the format of the Manufacturer ID data.

Table 8-2. Manufacturer ID Data Format

Device	Manufacturer Code <d23:d12></d23:d12>	Device Code <d11:d3></d11:d3>	Revision Code <d2:d0></d2:d0>	Hex Value <d23:d0></d23:d0>
AT21CS01	0000-0000-1101	0010-0000-0	000	00D200h
AT21CS11	0000-0000-1101	0011-1000-0	000	00D380h

The Manufacturer Identifier portion of the ID is returned in the 12 Most Significant bits of the three bytes read out. The value reserved for Microchip is 0000-0000-1101b (00Dh). Therefore, the first byte read out by the device will be 00h. The upper nibble of the second byte read out is Dh.

The Least Significant 12 bits of the 24-bit ID is comprised of a Microchip defined value that indicates the device density and revision. Bits D11 through D3 indicate the device code and bits D2 through D0 indicate the device revision. The output is shown more specifically in Table 8-2.

The overall 24-bit value returned by the AT21CS01 is 00D200h. The overall 24-bit value returned by the AT21CS11 is 00D380h.

# 9. ROM Zones

# 9.1 ROM Zone Size and ROM Zone Registers

Certain applications require that portions of the EEPROM memory array be permanently protected against malicious attempts at altering program code, data modules, security information, or encryption/decryption algorithms, keys, and routines. To address these applications, the memory array is segmented into four different memory zones of 256 bits each. A ROM Zone mechanism has been incorporated that allows any combination of individual memory zones to be permanently locked so that they become read-only (ROM). Once a memory zone has been converted to ROM, it can never be erased or programmed again, and it can never be unlocked from the ROM state. Table 9-2 shows the address range of each of the four memory zones.

### 9.1.1 ROM Zone Registers

Each 256-bit memory zone has a corresponding single-bit ROM Zone register that is used to control the ROM status of that zone. These registers are nonvolatile and will retain their state even after a device power cycle or Reset operation. The following table outlines the two states of the ROM Zone registers. Each ROM Zone register has specific ROM Zone register address that is reserved for read or write access.

Table 9-1. ROM Zone Register Values

Value	ROM Zone Status
0	ROM Zone is not enabled and that memory zone can be programmed and erased (the default state).
1	ROM Zone is enabled and that memory zone can never be programmed or erased again.

Issuing the ROM Zone command to a particular ROM Zone register address will set the corresponding ROM Zone register to the logic '1' state. Each ROM Zone register can only be set once; therefore, once set to the logic '1' state, a ROM Zone cannot be reset back to the logic '0' state.

Table 9-2. ROM Zone Address Ranges

Memory Zone	Starting Memory Address	Ending Memory Address	ROM Zone Register Address
0	0h	1Fh	01h
1	20h	3Fh	02h
2	40h	5Fh	04h
3	60h	7Fh	08h

# 9.2 Programming and Reading the ROM Zone Registers

### 9.2.1 Reading the Status of a ROM Zone Register

To check the current status of a ROM Zone register, the master must emulate a random read sequence with the exception that the opcode <code>0111b</code> (7h) will be used. The dummy write portion of the random read sequence is needed to specify which ROM Zone register address is to be read.

This sequence begins by the master sending a Start condition, followed by a device address byte with the opcode of 7h in the four Most Significant bits, along with the appropriate slave address combination and the Read/Write bit set to a logic '0'. The AT21CS01/AT21CS11 will respond with an ACK.


Following this device address byte is an 8-bit ROM Zone register address byte. The four Most Significant bits are not used and are therefore "don't care" bits. The address sent to the device must match one of the ROM Zone register addresses specified in Table 9-2. After the ROM Zone register address has been sent, the AT21CS01/AT21CS11 will return an ACK (logic '0').

Then an additional Start condition is sent to the device with the same device address byte as before, but now with the Read/Write bit set to a logic '1', to which the device will return an ACK. After the AT21CS01/AT21CS11 has sent the ACK, the device will output either 00h or FFh data byte. A 00h data byte indicates that the ROM Zone register is zero, meaning the zone has not been set as ROM. If the device outputs FFh data, then the memory zone has been set to ROM and cannot be altered.

Table 9-3. Read ROM Zone Register - Output Data

Output Data	ROM Zone Register Value			
00h	ROM Zone register value is zero (zone is not set as ROM).			
FFh	ROM Zone register value is one (zone is permanently set as ROM).			

Figure 9-1. Reading the State of a ROM Zone Register



### 9.2.2 Writing to a ROM Zone Register

A ROM Zone register can only be written to a logic '1' which will set the corresponding memory zone to a ROM state. Once a ROM Zone register has been written, it can never be altered again.

To write to a ROM Zone register, the master must send a Start condition, followed by the device address byte with the opcode of 0111b (7h) specified, along with the appropriate slave address combination and the Read/Write bit set to a logic '0'. The device will return an ACK. After the device address byte has been sent, the AT21CS01/AT21CS11 will return an ACK.

Following the device address byte is an 8-bit ROM Zone register address byte. The address sent to the device must match one of the ROM Zone register addresses specified in Table 9-2. After the ROM Zone register address has been sent, the AT21CS01/AT21CS11 will return an ACK.

After the AT21CS01/AT21CS11 has sent the ACK, the master must send an FFh data byte in order to set the appropriate ROM Zone register to the logic '1' state. The device will then return an ACK and, after a Stop condition is executed, the device will enter a self-time internal write cycle, lasting  $t_{WR}$ . If a Stop condition is sent at any other point in the sequence, the write operation to the ROM Zone register is aborted. The device will not respond to any commands until the  $t_{WR}$  time has completed. This sequence is depicted in Figure 9-2.

Figure 9-2. Writing to a ROM Zone Register



**Note:** Any attempt to interrupt the internal write cycle by driving the SI/O line low may cause the register being programmed to become corrupted. Refer to Device Behavior During Internal Write Cycle for the behavior of the device while a write cycle is in progress. If the master must interrupt a write operation, the SI/O line must be driven low for t<sub>DSCHG</sub> as noted in Interrupting the Device during an Active Operation.

#### 9.2.3 Freeze ROM Zone Registers

The current ROM Zone state can be frozen so that no further modifications to the ROM Zone registers can be made. Once frozen, this event cannot be reversed.

To freeze the state of the ROM Zone registers, the master must send a Start condition, followed by the device address byte with the opcode of 0001b (1h) specified, along with the appropriate slave address combination and the Read/Write bit set to a logic '0'. The device will return either an ACK (logic '0') response if the ROM Zone registers have not been previously frozen or a NACK (logic '1') response if the registers have already been frozen.

If the AT21CS01/AT21CS11 returns an ACK, the master must send a fixed arbitrary address byte value of 55h, to which the device will return an ACK (logic '0'). Following the 55h address byte, a data byte of AAh must be sent by the master. The device will ACK after the AAh data byte. If an address byte other than 55h or a data byte other than AAh is sent, the device will NACK (logic '1') and the freeze operation will not be performed.

To complete the Freeze ROM Zone register sequence, a Stop condition is required. If a Stop condition is sent at any other point in this sequence, the operation is aborted. Since a Stop condition is defined as a null bit frame with SI/O pulled high, the master does not need to drive the SI/O line to accomplish this. After the Stop condition is complete, the internally self-timed write cycle will begin. The SI/O pin must be pulled high via the external pull-up resistor during the entire  $t_{WR}$  cycle.

Figure 9-3. Freezing the ROM Zone Registers



**Note:** Any attempt to drive the SI/O line low during the t<sub>WR</sub> time period may cause the Freeze operation to not complete successfully, and must be avoided.

# 9.3 Device Response to a Write Operation Within an Enabled ROM Zone

The AT21CS01/AT21CS11 will respond differently to a write operation in a memory zone that has been set to ROM compared to write operation in a memory zone that has not been set to ROM. Writing to the EEPROM is accomplished by sending a Start condition followed by a device address byte with the opcode of 1010b (Ah), the appropriate slave address combination, and the Read/Write bit set as a logic '0'. Since a memory address has not been input at this point in the sequence, the device returns an ACK. Next, the 8-bit word address is sent which will result in an ACK from the device, regardless if that address is in a memory zone that has been set to ROM. However, upon sending the data input byte, a write operation to an address that was in a memory zone that was set to ROM will result in a NACK response from the AT21CS01/AT21CS11 and the device will be immediately ready to accept a new command. If the address being written was in a memory zone that had not been set to ROM, the device will return an ACK to the data input byte as per normal operation for write operations as described in Write Operations.

# AT21CS01/AT21CS11

# **Device Default Condition from Microchip**


10. Device Default Condition from	ı Microchip
-----------------------------------	-------------

The AT21CS01/AT21CS11 is delivered with the EEPROM array set to logic '1', resulting in FFh data in all locations.


# 11. Packaging Information

# 11.1 Package Marking Information

# AT21CS01 and AT21CS11: Package Marking Information




AT21CS01 Truncation Code ###: K1M							
AT21CS11 Truncation Code ###: K2							
Date Codes	3				Slave Address		
YY = Year 17: 2017	21: 2021	Y = Year 7: 2017	1: 2021	WW = Work Week of Assembly 02: Week 2	% = Slave Addre A: Address 000	ss E: Address 100	
18: 2018 19: 2019 20: 2020	22: 2022 23: 2023 24: 2024	8: 2018 9: 2019 0: 2020	2: 2022 3: 2023 4: 2024	04: Week 2 04: Week 4  52: Week 52	B: Address 001	F: Address 100 G: Address 110 H: Address 111	
Country of	Origin		Device	Grade	Atmel Truncation	on	
CO = Count	ry of Origin		H or U:	Industrial Grade	AT: Atmel ATM: Atmel ATML: Atmel		
Lot Numbe	r or Trace Co	ode			l		





**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging.

# 3-Lead Plastic Small Outline Transistor (TT) [SOT-23]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging








Microchip Technology Drawing C04-104 (TT) Rev C Sheet 1 of 2

# 3-Lead Plastic Small Outline Transistor (TT) [SOT-23]

For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



	N	1ILLIMETER:	S	
Dimensior	MIN	NOM	MAX	
Number of Pins	N		3	
Lead Pitch	е		0.95 BSC	
Outside Lead Pitch	e1		1.90 BSC	
Overall Height	Α	0.89	-	1.12
Molded Package Thickness	A2	0.79	0.95	1.02
Standoff	A1	0.01	-	0.10
Overall Width	Е	2.10	-	2.64
Molded Package Width	E1	1.16	1.30	1.40
Overall Length	D	2.67	2.90	3.05
Foot Length	L	0.13	0.50	0.60
Footprint (L1)		0.42 REF		
Foot Angle	φ	0°	-	10°
Lead Thickness	С	0.08 - 0.20		
Lead Width	b	0.30	-	0.54

#### Notes:

Note:

- Dimensions D and E1 do not include mold flash or protrusions. Mold flash or protrusions shall not exceed 0.127mm per side.
- 2. Dimensioning and tolerancing per ASME Y14.5M


BSC: Basic Dimension. Theoretically exact value shown without tolerances.

REF: Reference Dimension, usually without tolerance, for information purposes only.

Microchip Technology Drawing C04-104 (TT) Rev C Sheet 2 of 2

# 3-Lead Plastic Small Outline Transistor (TT) [SOT-23]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



# **RECOMMENDED LAND PATTERN**

	MILLIMETERS			
Dimension Limits		MIN	NOM	MAX
Contact Pitch	Е	0.95 BSC		
Contact Pad Spacing	С		2.30	
Contact Pad Width (X3)	X1			0.65
Contact Pad Length (X3)	Y1			1.10


#### Notes

- Dimensioning and tolerancing per ASME Y14.5M
   BSC: Basic Dimension. Theoretically exact value shown without tolerances.
- 2. For best soldering results, thermal vias, if used, should be filled or tented to avoid solder loss during reflow process

Microchip Technology Drawing C04-2104 (TT) Rev B

# 8-Lead Plastic Small Outline (SN) - Narrow, 3.90 mm Body [SOIC]


**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



Microchip Technology Drawing No. C04-057C Sheet 1 of 2

# 8-Lead Plastic Small Outline (SN) - Narrow, 3.90 mm Body [SOIC]

**lote:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



	MILLIMETERS			
Dimension	Limits	MIN	NOM	MAX
Number of Pins	N		8	
Pitch	е		1.27 BSC	
Overall Height	Α	•	ı	1.75
Molded Package Thickness	A2	1.25	ı	-
Standoff §	A1	0.10	ı	0.25
Overall Width E 6.00 BSC				
Molded Package Width	E1		3.90 BSC	
Overall Length	D	4.90 BSC		
Chamfer (Optional)	h	0.25	1	0.50
Foot Length	L	0.40 - 1.27		
Footprint	L1		1.04 REF	
Foot Angle	φ	0°	1	8°
Lead Thickness	С	0.17 - 0.25		
Lead Width	b	0.31		0.51
Mold Draft Angle Top	α	5° - 15°		
Mold Draft Angle Bottom	β	5°	-	15°

#### Notes:

- $\hbox{1. Pin 1 visual index feature may vary, but must be located within the hatched area.}\\$
- 2. § Significant Characteristic
- 3. Dimensions D and E1 do not include mold flash or protrusions. Mold flash or protrusions shall not exceed 0.15mm per side.
- 4. Dimensioning and tolerancing per ASME Y14.5M


BSC: Basic Dimension. Theoretically exact value shown without tolerances.

REF: Reference Dimension, usually without tolerance, for information purposes only.

Microchip Technology Drawing No. C04-057C Sheet 2 of 2

# 8-Lead Plastic Small Outline (SN) - Narrow, 3.90 mm Body [SOIC]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



RECOMMENDED LAND PATTERN


	Units	Jnits MILLIMETERS		S
Dimension	Limits	MIN	NOM	MAX
Contact Pitch	Е	1.27 BSC		
Contact Pad Spacing	С		5.40	
Contact Pad Width (X8)	X1			0.60
Contact Pad Length (X8)	Y1			1.55

#### Notes:

1. Dimensioning and tolerancing per ASME Y14.5M

BSC: Basic Dimension. Theoretically exact value shown without tolerances.

Microchip Technology Drawing No. C04-2057A



**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging.

# 12. Revision History

#### Revison D (June 2020)

Updated SOT23 package drawing to Microchip equivalent.

### Revision C (November 2019)

Revised Figure 4-5. Corrected AT21CS11 Manufacturer ID. Clarified marking details.

#### Revision B (March 2019)

Fixed typo for AT21CS11 Manufacturer ID. Corrected  $t_{RESET}$  timing from 48  $\mu s$  to 96  $\mu s$ . Updated Product Identification System section. Updated content throughout for clarification. Updated the 4-ball WLCSP and 3-lead SOT23 Package Outline Drawings. Updated SOIC package drawing to Microchip format.

#### Revision A (October 2017)

Updated to Microchip template. Microchip DS20005857 replaces Atmel documents 8903 and 8975. Added XSFN package. Updated DC output current absolute maximum rating. Removed lead finish designation. Updated trace code format in package markings.

#### Atmel AT21CS11 Document 8975 Revision B (November 2015)

Removed Standard Speed mode.

# Atmel AT21CS11 Document 8975 Revision A (August 2015)

Initial document release, Preliminary Status.

#### Atmel AT21CS01 Document 8903 Revision A (August 2015)

Initial document release.

# The Microchip Website

Microchip provides online support via our website at <a href="www.microchip.com/">www.microchip.com/</a>. This website is used to make files and information easily available to customers. Some of the content available includes:

- Product Support Data sheets and errata, application notes and sample programs, design resources, user's
  quides and hardware support documents, latest software releases and archived software
- General Technical Support Frequently Asked Questions (FAQs), technical support requests, online discussion groups, Microchip design partner program member listing
- Business of Microchip Product selector and ordering guides, latest Microchip press releases, listing of seminars and events, listings of Microchip sales offices, distributors and factory representatives

# **Product Change Notification Service**

Microchip's product change notification service helps keep customers current on Microchip products. Subscribers will receive email notification whenever there are changes, updates, revisions or errata related to a specified product family or development tool of interest.

To register, go to www.microchip.com/pcn and follow the registration instructions.

# **Customer Support**

Users of Microchip products can receive assistance through several channels:


- · Distributor or Representative
- · Local Sales Office
- Embedded Solutions Engineer (ESE)
- · Technical Support

Customers should contact their distributor, representative or ESE for support. Local sales offices are also available to help customers. A listing of sales offices and locations is included in this document.

Technical support is available through the website at: www.microchip.com/support

# **Product Identification System**

To order or obtain information, e.g., on pricing or delivery, refer to the factory or the listed sales office.



Note 1: Contact Microchip Sales non 0-0-0 Slave Address availability.

# Examples

Device	Package	Package Drawing Code	Package Option	Pull-Up Voltage	Shipping Carrier Option	Device Grade
AT21CS01-SSHM10-B	SOIC	SN	SS	1.7V to 3.6V	Bulk (Tubes)	
AT21CS11-SSH10-B	SOIC	SN	SS	2.7V to 4.5V	Bulk (Tubes)	
AT21CS01-SSHM10-T	SOIC	SN	SS	1.7V to 3.6V	Tape and Reel	
AT21CS01-SSH10-T	SOIC	SN	SS	2.7V to 4.5V	Tape and Reel	Industrial
AT21CS01-MSHM10-T	XSFN	2MS-1	MS	1.7V to 3.6V	Tape and Reel	Temperature
AT21CS01-MSH10-T	XSFN	2MS-1	MS	2.7V to 4.5V	Tape and Reel	(-40°C to +85°C)
AT21CS11-STUM10-T	SOT23	TT	ST	1.7V to 3.6V	Tape and Reel	
AT21CS11-STU10-T	SOT23	TT	ST	2.7V to 4.5V	Tape and Reel	
AT21CS01-UUM0B-T	WLCSP	4U-6	U	1.7V to 3.6V	Tape and Reel	

# Microchip Devices Code Protection Feature

Note the following details of the code protection feature on Microchip devices:

- Microchip products meet the specification contained in their particular Microchip Data Sheet.
- Microchip believes that its family of products is one of the most secure families of its kind on the market today, when used in the intended manner and under normal conditions.
- There are dishonest and possibly illegal methods used to breach the code protection feature. All of these
  methods, to our knowledge, require using the Microchip products in a manner outside the operating
  specifications contained in Microchip's Data Sheets. Most likely, the person doing so is engaged in theft of
  intellectual property.
- Microchip is willing to work with the customer who is concerned about the integrity of their code.
- Neither Microchip nor any other semiconductor manufacturer can guarantee the security of their code. Code protection does not mean that we are guaranteeing the product as "unbreakable."

Code protection is constantly evolving. We at Microchip are committed to continuously improving the code protection features of our products. Attempts to break Microchip's code protection feature may be a violation of the Digital Millennium Copyright Act. If such acts allow unauthorized access to your software or other copyrighted work, you may have a right to sue for relief under that Act.

# **Legal Notice**

Information contained in this publication regarding device applications and the like is provided only for your convenience and may be superseded by updates. It is your responsibility to ensure that your application meets with your specifications. MICROCHIP MAKES NO REPRESENTATIONS OR WARRANTIES OF ANY KIND WHETHER EXPRESS OR IMPLIED, WRITTEN OR ORAL, STATUTORY OR OTHERWISE, RELATED TO THE INFORMATION, INCLUDING BUT NOT LIMITED TO ITS CONDITION, QUALITY, PERFORMANCE, MERCHANTABILITY OR FITNESS FOR PURPOSE. Microchip disclaims all liability arising from this information and its use. Use of Microchip devices in life support and/or safety applications is entirely at the buyer's risk, and the buyer agrees to defend, indemnify and hold harmless Microchip from any and all damages, claims, suits, or expenses resulting from such use. No licenses are conveyed, implicitly or otherwise, under any Microchip intellectual property rights unless otherwise stated.

### **Trademarks**

The Microchip name and logo, the Microchip logo, Adaptec, AnyRate, AVR, AVR logo, AVR Freaks, BesTime, BitCloud, chipKIT, chipKIT logo, CryptoMemory, CryptoRF, dsPIC, FlashFlex, flexPWR, HELDO, IGLOO, JukeBlox, KeeLoq, Kleer, LANCheck, LinkMD, maXStylus, maXTouch, MediaLB, megaAVR, Microsemi, Microsemi logo, MOST, MOST logo, MPLAB, OptoLyzer, PackeTime, PIC, picoPower, PICSTART, PIC32 logo, PolarFire, Prochip Designer, QTouch, SAM-BA, SenGenuity, SpyNIC, SST, SST Logo, SuperFlash, Symmetricom, SyncServer, Tachyon, TempTrackr, TimeSource, tinyAVR, UNI/O, Vectron, and XMEGA are registered trademarks of Microchip Technology Incorporated in the U.S.A. and other countries.

APT, ClockWorks, The Embedded Control Solutions Company, EtherSynch, FlashTec, Hyper Speed Control, HyperLight Load, IntelliMOS, Libero, motorBench, mTouch, Powermite 3, Precision Edge, ProASIC, ProASIC Plus, ProASIC Plus logo, Quiet-Wire, SmartFusion, SyncWorld, Temux, TimeCesium, TimeHub, TimePictra, TimeProvider, Vite, WinPath, and ZL are registered trademarks of Microchip Technology Incorporated in the U.S.A.

Adjacent Key Suppression, AKS, Analog-for-the-Digital Age, Any Capacitor, Anyln, AnyOut, BlueSky, BodyCom, CodeGuard, CryptoAuthentication, CryptoAutomotive, CryptoCompanion, CryptoController, dsPICDEM, dsPICDEM.net, Dynamic Average Matching, DAM, ECAN, EtherGREEN, In-Circuit Serial Programming, ICSP, INICnet, Inter-Chip Connectivity, JitterBlocker, KleerNet logo, memBrain, Mindi, MiWi, MPASM, MPF, MPLAB Certified logo, MPLIB, MPLINK, MultiTRAK, NetDetach, Omniscient Code Generation, PICDEM, PICDEM.net, PICkit, PICtail, PowerSmart, PureSilicon, QMatrix, REAL ICE, Ripple Blocker, SAM-ICE, Serial Quad I/O, SMART-I.S., SQI, SuperSwitcher, SuperSwitcher II, Total Endurance, TSHARC, USBCheck, VariSense, ViewSpan, WiperLock, Wireless DNA, and ZENA are trademarks of Microchip Technology Incorporated in the U.S.A. and other countries.

SQTP is a service mark of Microchip Technology Incorporated in the U.S.A.

The Adaptec logo, Frequency on Demand, Silicon Storage Technology, and Symmcom are registered trademarks of Microchip Technology Inc. in other countries.

GestIC is a registered trademark of Microchip Technology Germany II GmbH & Co. KG, a subsidiary of Microchip Technology Inc., in other countries.

All other trademarks mentioned herein are property of their respective companies.

© 2020, Microchip Technology Incorporated, Printed in the U.S.A., All Rights Reserved.

ISBN: 978-1-5224-6242-2

AMBA, Arm, Arm7, Arm7TDMI, Arm9, Arm11, Artisan, big.LITTLE, Cordio, CoreLink, CoreSight, Cortex, DesignStart, DynamIQ, Jazelle, Keil, Mali, Mbed, Mbed Enabled, NEON, POP, RealView, SecurCore, Socrates, Thumb, TrustZone, ULINK, ULINK2, ULINK-ME, ULINK-PLUS, ULINKpro, µVision, Versatile are trademarks or registered trademarks of Arm Limited (or its subsidiaries) in the US and/or elsewhere.

# **Quality Management System**

For information regarding Microchip's Quality Management Systems, please visit www.microchip.com/quality.



# **Worldwide Sales and Service**

AMERICAS         ASIA/RACIFIC         ASIA/RACIFIC         EUROPE           2355 West Chandler Blud         Tel: 61-2-9868-6733         India - Bangalore         Tel: 43-7242-2244-39           Chandler, AZ 55/24-6199         China - Beijing         India - New Delhi         Fex: 43-7242-2244-39           Fax: 480-792-7200         Tel: 86-10-8669-7000         Tel: 91-80-3080-4444         Tel: 43-7242-2244-39           Fax: 480-792-7270         China - Chengdu         India - Pune         Tel: 91-11-1141         Fex: 43-7242-2244-39           Fax: 480-792-7270         China - Chengdu         India - Pune         Tel: 91-20-412-10141         Fex: 44-485-5910           Technical Support:         Www.microtip.com/Support         China - Chongqiing         Tel: 91-20-412-10141         Fex: 45-4485-229           Allanta         Tel: 86-87-88-902-980         China - Chonggue         Japan - Tokyo         France - Paris           Fax: 678-98-79-961         Tel: 86-87-89-802-9         Tel: 81-3-688-80-3770         Tel: 33-1-69-3-58-50-0           Fex: 578-98-71-455         China - Hangshou         Korea - Daegu         Fex: 33-1-69-3-58-50-0           Tel: 678-98-79-814         Tel: 88-87-18-928-815         Tel: 82-25-44-4001         Germany - Hann           Tel: 578-78-89-71-155         China - Hangkou         Korea - Seoul         Tel: 82-35-36-700				
2355 West Chandler Blvd.   Tel. 61-2-898-6733   Tel. 91-80-3090-4444   Ind. 4-87-242-2244-39   Tel. 480-792-7270   Tel. 86-10-8568-7000   Tel. 86-10-8568-7000   Tel. 86-10-8568-7000   Tel. 86-10-8568-7000   Tel. 86-10-8568-7000   Tel. 86-10-8568-7000   Tel. 91-11-4160-8631   Demark - Copenhagen   Tel. 48-4485-5910   Tel. 48-4485-5910   Tel. 49-4485-5910   Tel. 86-24-8890-588   Tel. 86-28-88980-588   Tel. 86-28-88980-588   Tel. 86-28-88980-588   Tel. 86-28-88980-588   Tel. 86-28-8899-588   Tel. 86-28-8890-588   Tel. 86-28-8890-588   Tel. 86-28-8890-588   Tel. 86-28-8890-588   Tel. 86-28-8890-588   Tel. 86-28-88-880-788   Tel. 86-28-88-880-988   Tel. 86-28-87-8800   Tel. 86-28-8800   Tel. 86-2	AMERICAS	ASIA/PACIFIC	ASIA/PACIFIC	EUROPE
Chandler, AZ 85224-8199   Tell: 480-792-7277   Tell: 480-898-9808   Tell: 480-898-9808   Tell: 480-898-9888   Tell: 480-898-9889   Tell: 480-898-989   Tell: 480-898-9889   Tell: 480-898-989   Tell: 480-	Corporate Office	Australia - Sydney	India - Bangalore	Austria - Wels
Tel: 48-07-782-7200	2355 West Chandler Blvd.	Tel: 61-2-9868-6733	Tel: 91-80-3090-4444	Tel: 43-7242-2244-39
Fax: 480-792-7277	Chandler, AZ 85224-6199	China - Beijing	India - New Delhi	Fax: 43-7242-2244-393
Technical Support	Tel: 480-792-7200	Tel: 86-10-8569-7000	Tel: 91-11-4160-8631	Denmark - Copenhagen
New Microchip cond   Sepo	Fax: 480-792-7277	China - Chengdu	India - Pune	Tel: 45-4485-5910
Web Address:	Technical Support:	Tel: 86-28-8665-5511	Tel: 91-20-4121-0141	Fax: 45-4485-2829
Atlanta	www.microchip.com/support	China - Chongqing	Japan - Osaka	Finland - Espoo
Atlanta	Web Address:	Tel: 86-23-8980-9588	Tel: 81-6-6152-7160	Tel: 358-9-4520-820
Duluth, CA	www.microchip.com	China - Dongguan	Japan - Tokyo	France - Paris
Tel: 68-08-79-614	Atlanta	Tel: 86-769-8702-9880	Tel: 81-3-6880- 3770	Tel: 33-1-69-53-63-20
Fax: 678-957-1455	Duluth, GA	China - Guangzhou	Korea - Daegu	Fax: 33-1-69-30-90-79
Austin, TX	Tel: 678-957-9614	Tel: 86-20-8755-8029	Tel: 82-53-744-4301	Germany - Garching
Tel: 512-257-3370	Fax: 678-957-1455	China - Hangzhou	Korea - Seoul	Tel: 49-8931-9700
Boston	Austin, TX	Tel: 86-571-8792-8115	Tel: 82-2-554-7200	Germany - Haan
Westborough, MA	Tel: 512-257-3370	China - Hong Kong SAR	Malaysia - Kuala Lumpur	Tel: 49-2129-3766400
Tel: 774-760-0087	Boston	Tel: 852-2943-5100	Tel: 60-3-7651-7906	Germany - Heilbronn
Fax: 774-760-0088	Westborough, MA	China - Nanjing	Malaysia - Penang	Tel: 49-7131-72400
Tel: 86-532-8502-7355   Tel: 86-32-634-9065   Germany - Munich	<del>-</del>	Tel: 86-25-8473-2460	Tel: 60-4-227-8870	Germany - Karlsruhe
Itasca, IL	Fax: 774-760-0088	China - Qingdao	Philippines - Manila	Tel: 49-721-625370
Tel: 630-285-0071 Fax: 630-285-0075 China - Shenyang Dallas Tel: 86-24-2334-2829 Tel: 86-24-2334-2829 Tel: 86-377-8366 Tel: 86-24-2334-2829 Tel: 86-377-8366 Tel: 972-818-7423 Tel: 86-755-8864-2200 Tel: 886-3-77-8360 Tel: 886-3-77-8380 Tel: 972-9744-7705 Tel: 972-818-7423 Tel: 86-755-8864-2200 Tel: 886-7-213-7830 Tel: 972-9-744-7705 Tel: 972-9-744-7705 Tel: 86-755-8864-2200 Tel: 886-7-213-7830 Tel: 972-9-744-7705 Tel: 972-9-744-7705 Tel: 86-755-8864-2200 Tel: 886-7-213-7830 Tel: 972-9-744-7705 Tel: 972-9-744-7705 Tel: 86-755-8864-2200 Tel: 886-7-213-7830 Tel: 972-9-744-7705 Tel: 98-24-8081-8000 Tel: 86-186-6233-1526 Novi, MI China - Wuhan Tel: 86-88-80600 Tel: 86-233-1526 Tel: 86-25-898-1351 Vietnam - Ho Chi Minh Tel: 38-4-8883 Tel: 86-29-8833-7252 Tel: 86-29-8833-7252 Tel: 31-773-8323 China - Xiamen Noblesville, INI Tel: 86-59-2388138 Tel: 317-738-2330 Tel: 317-738-2330 Tel: 317-738-2330 Tel: 317-738-2330 Tel: 317-536-2380 Los Angeles Los Angeles Los Angeles Los Angeles Raisel, NC Tel: 949-462-9503 Tel: 949-462-9503 Tel: 949-462-9608 Tel: 919-844-7510 New York, NY Tel: 919-844-7510 New York, NY Tel: 63-1-36000 San Jose, CA Tel: 408-735-9110 Tel: 408-735-9110 Tel: 408-735-9110 Tel: 408-735-9110 Tel: 408-735-9100 Tel: 905-695-1980	Chicago	Tel: 86-532-8502-7355	Tel: 63-2-634-9065	Germany - Munich
Fax: 630-285-0075	_	China - Shanghai	Singapore	<del>-</del>
Dallas	Tel: 630-285-0071	Tel: 86-21-3326-8000		Fax: 49-89-627-144-44
Dallas	Fax: 630-285-0075	China - Shenyang	Taiwan - Hsin Chu	Germany - Rosenheim
Tel: 972-818-7423 Tel: 86-755-8864-2200 China - Suzhou Tel: 86-86-2-5980-8600 Tel: 86-86-2-5980-5300 Tel: 86-2-698-8600 Tel: 86-2-698-8600 Tel: 39-0331-42611 Tel: 39-039-3031-426781 Tel: 39-039-3031-426781 Tel: 39-039-7625286 Tel: 31-77-3-8323 Tel: 31-77-3-8323 Tel: 31-77-3-8323 Tel: 31-77-3-8323 Tel: 86-592-2388138 Tel: 317-773-5453 Tel: 86-592-2388138 Tel: 317-773-5453 Tel: 86-756-3210040 Tel: 86-756-3210040 Tel: 39-034-75-360 Tel: 49-462-9523 Tel: 40-21-407-87-50 Tel: 99-844-7510 Tel: 99-844-7510 Tel: 99-844-7510 Tel: 408-73-9110 Tel: 408-735-9110 Tel: 408-735-9110 Tel: 408-735-9110 Tel: 408-735-9110 Tel: 408-735-9110 Tel: 408-735-9110 Tel: 408-735-9180	Dallas		Tel: 886-3-577-8366	<del>-</del>
Tel: 972-818-7423 Tel: 972-818-7423 Tel: 86-755-8864-2200 China - Suzhou Tel: 86-86-32-31526 Tel: 86-86-32-31526 Tel: 86-86-32-31526 Tel: 86-86-22-31-742611 Tel: 248-848-4000 Tel: 36-27-5980-5300 Tel: 36-2-698-8600 Tel: 39-0331-742611 Tel: 39-031-742611 Tel: 39-0331-742611 Tel: 39-0331-742611 Tel: 39-0331-742611 Tel: 39-0331-742611 Tel: 39-0331-74261 Netterland Tel: 39-0331-74261 Netterland Tel: 39-0331-74261 Netterland Tel: 39-0331-74261 Tel: 39-0331-74260 Tel: 39-0331-74261 Tel: 39-0331-74261 Tel: 39-0331-74261 Tel: 39-0331-74261 Tel: 39-0331-74261 Tel: 39-0331-74261 Tel: 39-031-74261 Tel: 39-031-7	Addison, TX	China - Shenzhen	Taiwan - Kaohsiung	Israel - Ra'anana
Detroit   Tel: 86-186-6233-1526   Tel: 886-2-2508-8600   Tel: 39-0331-742611   Novi, MI   China - Wuhan   Tel: 86-27-5980-5300   Tel: 66-2-694-1351   Italy - Padova   Houston, TX   China - Xian   Vietnam - Ho Chi Minh   Tel: 39-049-7625286   Tel: 86-29-8833-7252   Tel: 86-29-8833-7252   Tel: 86-29-8833-7252   Tel: 86-29-8833-7252   Tel: 84-28-5448-2100   Netherlands - Drunen   Tel: 31-416-690399   Fax: 31-416-690340   Tel: 31-773-8323   China - Zhuhai   Tel: 31-773-5453   Tel: 86-756-3210040   Tel: 86-756-3210040   Tel: 86-756-3210040   Tel: 951-273-7800   Tel: 631-435-6000   San Jose, CA   Tel: 408-735-9110   Tel: 408-735-9110   Tel: 408-335-9110   Tel: 408-345-900   Fax: 44-118-921-5800   Tel: 905-695-1980   Tel: 905-705-705-705-705	Tel: 972-818-7423	Tel: 86-755-8864-2200		Tel: 972-9-744-7705
Detroit	Fax: 972-818-2924	China - Suzhou	Taiwan - Taipei	Italy - Milan
Tel: 248-848-4000 Houston, TX China - Xian Tel: 281-894-5983 Tel: 86-29-8833-7252 Indianapolis China - Xiamen Noblesville, IN Tel: 34-66-90399 Noblesville, IN Tel: 86-592-2388138 Tel: 86-592-2388138 Tel: 86-756-3210040 Tel: 31-773-8453 Tel: 86-756-3210040 Tel: 31-773-8453 Tel: 86-756-3210040 Tel: 31-73-80-2380 Los Angeles Mission Viejo, CA Tel: 949-462-9523 Tel: 949-462-9608 Tel: 941-273-7800 Raleigh, NC Tel: 919-844-7510 New York, NY Tel: 631-435-6000 San Jose, CA Tel: 408-735-9110 Tel: 408-735-9110 Tel: 408-735-9100 Tel: 408-336-4270 Canada - Toronto Tel: 905-695-1980  Tel: 905-695-1980  Tel: 66-2-694-1351 Vietnam - Ho Chi Minh Tel: 39-049-7625286 Tel: 39-049-7625286 Tel: 39-049-7625286 Tel: 39-049-7625286 Tel: 34-28-5448-2100 Netterlands - Drunen Tel: 31-416-690399 Netterlands - Drunen Tel: 31-416-690399 Fax: 31-416-690340 Tel: 34-126-690399 Fax: 31-416-690340 Tel: 34-126-690399 Fax: 31-416-690340 Tel: 48-22-3325737 Romania - Bucharest Tel: 40-21-407-87-50 Spain - Madrid Tel: 48-22-3325737 Romania - Bucharest Tel: 40-21-407-87-50 Spain - Madrid Tel: 34-91-708-08-90 Fax: 34-91-708-08-91 Tel: 46-31-704-60-40 Sweden - Stockholm Tel: 46-31-704-60-40 Sweden - Stockholm Tel: 48-8-5090-4654 UK - Wokingham Tel: 44-118-921-5800 Fax: 44-118-921-5800	Detroit	Tel: 86-186-6233-1526	Tel: 886-2-2508-8600	Tel: 39-0331-742611
Houston, TX	Novi, MI	China - Wuhan		Fax: 39-0331-466781
Houston, TX	Tel: 248-848-4000	Tel: 86-27-5980-5300	Tel: 66-2-694-1351	Italy - Padova
Indianapolis	Houston, TX	China - Xian	Vietnam - Ho Chi Minh	Tel: 39-049-7625286
Noblesville, IN Tel: 86-592-2388138 China - Zhuhai Tel: 317-773-8323 Tel: 317-773-5453 Tel: 86-756-3210040 Tel: 47-72884388 Tel: 47-72884388 Tel: 48-22-3325737 Mission Viejo, CA Tel: 949-462-9523 Fax: 949-462-9608 Tel: 951-273-7800 Raleigh, NC Tel: 919-844-7510 New York, NY Tel: 631-435-6000 San Jose, CA Tel: 408-735-9110 Tel: 408-436-4270 Canada - Toronto Tel: 905-695-1980  Tel: 905-695-1980  Tel: 86-756-3210040 Tel: 46-31-704-60-340 Tel: 47-72884388 Poland - Warsaw Tel: 47-72884388 Poland - Warsaw Tel: 47-72884388 Poland - Warsaw Tel: 48-22-3325737 Romania - Bucharest Tel: 40-21-407-87-50 Spain - Madrid Tel: 40-21-407-87-50 Spain - Madrid Tel: 34-91-708-08-90 Fax: 34-91-708-08-91 Tel: 46-31-704-60-40 Tel: 46-31-704-60-40 Tel: 46-8-5090-4654 UK - Wokingham Tel: 44-118-921-5820	Tel: 281-894-5983	Tel: 86-29-8833-7252	Tel: 84-28-5448-2100	Netherlands - Drunen
Tel: 317-773-8323	Indianapolis	China - Xiamen		Tel: 31-416-690399
Fax: 317-773-5453 Tel: 86-756-3210040 Tel: 47-72884388 Poland - Warsaw Tel: 48-22-3325737 Romania - Bucharest Tel: 949-462-9523 Fax: 949-462-9608 Tel: 951-273-7800 Raleigh, NC Tel: 919-844-7510 New York, NY Tel: 631-435-6000 San Jose, CA Tel: 408-735-9110 Tel: 408-735-9110 Tel: 408-436-4270 Canada - Toronto Tel: 905-695-1980  Tel: 86-756-3210040  Tel: 86-756-3210040  Tel: 86-756-3210040  Tel: 48-22-3325737 Romania - Bucharest Tel: 40-21-407-87-50 Spain - Madrid Tel: 40-21-407-87-50 Spain - Madrid Tel: 34-91-708-08-90 Fax: 34-91-708-08-91 Sweden - Gothenberg Tel: 46-31-704-60-40 Sweden - Stockholm Tel: 408-735-9110 Tel: 408-735-9110 Tel: 408-735-9110 Tel: 408-136-4270 Tel: 408-735-9180	Noblesville, IN	Tel: 86-592-2388138		Fax: 31-416-690340
Fax: 317-773-5453       Tel: 86-756-3210040       Tel: 47-72884388         Tel: 317-536-2380       Poland - Warsaw         Los Angeles       Tel: 48-22-3325737         Mission Viejo, CA       Romania - Bucharest         Tel: 949-462-9523       Tel: 40-21-407-87-50         Fax: 949-462-9608       Spain - Madrid         Tel: 951-273-7800       Tel: 34-91-708-08-90         Raleigh, NC       Fax: 34-91-708-08-91         Tel: 919-844-7510       Sweden - Gothenberg         New York, NY       Tel: 46-31-704-60-40         Tel: 631-435-6000       Sweden - Stockholm         Tel: 408-735-9110       UK - Wokingham         Tel: 408-436-4270       Tel: 44-118-921-5800         Canada - Toronto       Fax: 44-118-921-5820	Tel: 317-773-8323	China - Zhuhai		Norway - Trondheim
Los Angeles       Tel: 48-22-3325737         Mission Viejo, CA       Romania - Bucharest         Tel: 949-462-9523       Tel: 40-21-407-87-50         Fax: 949-462-9608       Spain - Madrid         Tel: 951-273-7800       Tel: 34-91-708-08-90         Raleigh, NC       Fax: 34-91-708-08-91         Tel: 919-844-7510       Sweden - Gothenberg         New York, NY       Tel: 46-31-704-60-40         Tel: 631-435-6000       Sweden - Stockholm         San Jose, CA       Tel: 408-735-9110         Tel: 408-436-4270       UK - Wokingham         Tel: 408-436-4270       Fax: 44-118-921-5800         Canada - Toronto       Fax: 44-118-921-5820	Fax: 317-773-5453	Tel: 86-756-3210040		
Mission Viejo, CA Tel: 949-462-9523 Fax: 949-462-9608 Tel: 951-273-7800 Raleigh, NC Tel: 919-844-7510 New York, NY Tel: 631-435-6000 San Jose, CA Tel: 408-735-9110 Tel: 408-436-4270 Canada - Toronto Tel: 905-695-1980	Tel: 317-536-2380			Poland - Warsaw
Tel: 949-462-9523 Fax: 949-462-9608 Tel: 951-273-7800 Raleigh, NC Tel: 919-844-7510 New York, NY Tel: 631-435-6000 San Jose, CA Tel: 408-735-9110 Tel: 408-436-4270 Canada - Toronto Tel: 905-695-1980  Tel: 40-21-407-87-50 Spain - Madrid Tel: 34-91-708-08-90 Fax: 34-91-708-08-91 Sweden - Gothenberg Tel: 46-31-704-60-40 Sweden - Stockholm Tel: 46-8-5090-4654 UK - Wokingham Tel: 44-118-921-5800 Fax: 44-118-921-5820	Los Angeles			Tel: 48-22-3325737
Tel: 949-462-9523 Fax: 949-462-9608 Tel: 951-273-7800 Raleigh, NC Tel: 919-844-7510 New York, NY Tel: 631-435-6000 San Jose, CA Tel: 408-735-9110 Tel: 408-436-4270 Canada - Toronto Tel: 905-695-1980  Tel: 40-21-407-87-50 Spain - Madrid Tel: 34-91-708-08-90 Fax: 34-91-708-08-91 Sweden - Gothenberg Tel: 46-31-704-60-40 Sweden - Stockholm Tel: 46-8-5090-4654 UK - Wokingham Tel: 44-118-921-5800 Fax: 44-118-921-5820	Mission Viejo, CA			Romania - Bucharest
Tel: 951-273-7800  Raleigh, NC  Tel: 919-844-7510  New York, NY  Tel: 631-435-6000  San Jose, CA  Tel: 408-735-9110  Tel: 408-436-4270  Canada - Toronto  Tel: 905-695-1980  Tel: 34-91-708-08-90  Fax: 34-91-708-08-90  Fax: 34-91-708-08-90  Sweden - Gothenberg  Tel: 46-31-704-60-40  Sweden - Stockholm  Tel: 46-8-5090-4654  UK - Wokingham  Tel: 44-118-921-5800	=			Tel: 40-21-407-87-50
Raleigh, NC       Fax: 34-91-708-08-91         Tel: 919-844-7510       Sweden - Gothenberg         New York, NY       Tel: 46-31-704-60-40         Tel: 631-435-6000       Sweden - Stockholm         San Jose, CA       Tel: 46-8-5090-4654         Tel: 408-735-9110       UK - Wokingham         Tel: 408-436-4270       Tel: 44-118-921-5800         Canada - Toronto       Fax: 44-118-921-5820         Tel: 905-695-1980       Tel: 44-118-921-5820	Fax: 949-462-9608			Spain - Madrid
Raleigh, NC       Fax: 34-91-708-08-91         Tel: 919-844-7510       Sweden - Gothenberg         New York, NY       Tel: 46-31-704-60-40         San Jose, CA       Sweden - Stockholm         Tel: 408-735-9110       UK - Wokingham         Tel: 408-436-4270       Tel: 44-118-921-5800         Canada - Toronto       Fax: 44-118-921-5820         Tel: 905-695-1980       Tel: 48-470-48-470	Tel: 951-273-7800			Tel: 34-91-708-08-90
New York, NY       Tel: 46-31-704-60-40         Tel: 631-435-6000       Sweden - Stockholm         San Jose, CA       Tel: 46-8-5090-4654         Tel: 408-735-9110       UK - Wokingham         Tel: 408-436-4270       Tel: 44-118-921-5800         Canada - Toronto       Fax: 44-118-921-5820         Tel: 905-695-1980       Fax: 44-118-921-5820				Fax: 34-91-708-08-91
Tel: 631-435-6000 San Jose, CA Tel: 408-735-9110 Tel: 408-436-4270 Canada - Toronto Tel: 905-695-1980  Sweden - Stockholm Tel: 46-8-5090-4654 UK - Wokingham Tel: 44-118-921-5800 Fax: 44-118-921-5820	Tel: 919-844-7510			Sweden - Gothenberg
Tel: 631-435-6000       Sweden - Stockholm         San Jose, CA       Tel: 46-8-5090-4654         Tel: 408-735-9110       UK - Wokingham         Tel: 408-436-4270       Tel: 44-118-921-5800         Canada - Toronto       Fax: 44-118-921-5820         Tel: 905-695-1980       Fax: 44-118-921-5820	New York, NY			_
Tel: 408-735-9110 Tel: 408-436-4270 Canada - Toronto Tel: 905-695-1980  UK - Wokingham Tel: 44-118-921-5800 Fax: 44-118-921-5820	·			Sweden - Stockholm
Tel: 408-735-9110 Tel: 408-436-4270 Canada - Toronto Tel: 905-695-1980  UK - Wokingham Tel: 44-118-921-5800 Fax: 44-118-921-5820	San Jose, CA			Tel: 46-8-5090-4654
Tel: 408-436-4270 Tel: 44-118-921-5800 Canada - Toronto Tel: 905-695-1980 Tel: 905-695-1980				UK - Wokingham
Canada - Toronto         Fax: 44-118-921-5820           Tel: 905-695-1980         Fax: 44-118-921-5820				_
Tel: 905-695-1980				
FaX: 905-695-2078	Fax: 905-695-2078			